


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Russell County, Sec. 21 Twp. 12S Rge. 15 (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW&SW" or footage from lines. NW NE NW
Lease Owner Morris G. Veverka Oil Company
Lease Name Shaffer Well No. 1
Office Address P. O. Box 181, Plainville, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 1, 1962
Application for plugging filed February 1, 1962
Application for plugging approved February 1, 1962
Plugging commenced February 1, 1962
Plugging completed February 1, 1962
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	227'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,300 feet (RTD) to 420 feet. Set bottom plug at 420 feet and cemented with hulls and 20 sacks cement. Filled hole with heavy rotary mud to 190 feet. Set middle plug at 190 feet and cemented with hulls and 20 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set top plug and cemented with hulls and 10 sacks cement, filling hole to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
2-5-1962
FEB 5 1962
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 709 Petroleum Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick contractor
Priscilla M. Ismert (employee of H-30, Inc. or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Priscilla M. Ismert
709 Petroleum Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of February, 19 61

My commission expires December 3, 1964.
Geraldine Hays Notary Public.



15-167-00668-00-00
KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Normie C. Tevoria Oil Company**

SEC. **21** T. **12** R. **15**

FARM **Shaffer** NO. **1**

LOC. **H H H**

TOTAL DEPTH **3,300'**

COUNTY **Russell**

COMM. **1-21-62**


COMP. **2-1-62**

KANSAS

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED



CASING

20 10
 15 8 **3/8" 277' cemented w/175 wt.**
 12 6
 13 5

1789 CR
 ELEVATION **1791 IP**
1794 KI
 PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Rock	55
Clay and sand streaks	105
Shale	160
Shale and shells	227
Shale	290
Sand and Iron	381
Iron Pyrite & shale	405
Shale & Shells	829
Anhydrite	853
Shale & Shells	1470
Line and Shale	2082
Hard Line	2089
Line and Shale	3060
HC Line	3030
Line and Shale	3185
HC Line	3175
Line and Shale	3235
Cong. Chert	3300
Rotary Total Depth	3300

2-5-1962

Sample Tops

Anhydrite Top	820	+ 974
Anhydrite Base	853	+ 941
Topsoil	2792	- 998
Mer-omer	2910	- 1116
Kansas City	2960	- 1166
R. C. Co.	3300	- 1506

I hereby certify that the above and foregoing is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Priscilla M. Jernst
 Priscilla M. Jernst

(STATE OF KANSAS)
) ss:
 (RUSSELL COUNTY)

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 1st day of February, 1962.

Geraldine Hays
 Geraldine Hays, Notary Public

My Commission Expires:
 December 31, 1964.

