

4-041589

7-11

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-21,412-0000

SE SW NE /4 SEC. 36, 10 S, 17 W  
2970 feet from S section line  
1650 feet from E section line

Operator license# 8507 Lease Whisman well # 3

Operator: Paxco, Inc. County Rooks

Address: 8920 Peppertree Court Well total depth 3561 feet # 115.73  
Wichita, Kansas 67226 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 217 feet  
w/150 sxs.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing - Randy's Well Service License#    

Address: Russell, Kansas 67665 - Plainville, Kansas 67663

Company to plug at: Hour: 8:00A.M. Day: 11 Month: July Year: 94

Plugging proposal received from: Jamie Mendez

Company: Randy's Well Service Phone:    

Were: 4 1/2" casing set @ 3561' w/250 sxs. cmt. Perf. @ 3392'-3420'.  
Anhy. @ 1130' - Dakota @ 550' - Tubing sanded in and parted @ 907'.  
Casing parted. Ordered 200 sxs. common with 1/4# flocele plus ordered  
150 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.  
Booster pump pulled & tubing open to production zones prior to plugging.  
Tubing sanded in below 907'

Plugging Proposal Received by: Dennis Hamel - Herb Deines

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 11:30A.M., Day: 11, Month: July, Year: 94

Actual plugging report: Run in hole with tubing to 907'. Spot 100 sxs.  
common cement. Pulled tubing to 550'. Spot 30 sxs. cement to circulate  
at surface. Pulled tubing. Hooked-up to 4 1/2" casing - squeezed 70  
sxs. common plus 40 sxs. 60/40 posmix. Max. 600#. Hooked-up to  
8 5/8" S.P. Pressured up to Max. 1000# P.S.I.

RECEIVED  
STATE CORPORATION COMMISSION  
7-13-94  
JUL 13 1994

Remarks:      
Condition of casing(in hole): GOOD     BAD X Anhy. plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING X, CASING    . Elevation:     GL     Wichita, Kansas

I did [ X ] did not [     ] observe the plugging. Dennis L Hamel

DATE 7-21-94  
INV. NO. 40849

HD

(agent)  
Form CP-2/3