

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-21,998-0000

SE, Sec. 35, T 10 S, R 17W

990 feet from N section line

990 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5215

Lease Name WHISMAN Well # 1

Operator: LEE PHILLIPS OIL CO.
Name & Address 125 NO. MARKET #1532
WICHITA, KANS. 67202

County ROOMS.

Well Total Depth 3700 feet \$120.25

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor D.R. LAUCK OIL CO License Number 5427

Address 221 SO. BROADWAY #408 WICHITA, KANS. 67202

Company to plug at: Hour: 3:00 PM Day: 19th Month: APRIL Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO DOYL FOLMERS

(company name) D.R. LAUCK OIL CO (phone) 316-264-6392

were: 8 5/8" 249 ESP. OUL #1200 50% Formix-2% GEL-3% CA-CL. (BY HALCO)

ORDER 200 50% Formix 6% GEL-3% CA-CL. AND 8 5/8" PLUG

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

PENETRATED ARBUCKLE @ 3687' ANHYDRITE 1315'

Signed [Signature] (TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 PM Day: 19th Month: APRIL Year: 1983

ACTUAL PLUGGING REPORT

ORDERED - 200 50% Formix 6% GEL-3% CA-CL. AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 3630' / 20' CNT, 2nd PLUG @ 1320' / 20' CNT.

3rd PLUG @ 870' / 100' CNT, 4th PLUG @ 270' / 40' CNT.

5th PLUG @ HULL'S BRIDGE @ 40' to 0' / 10' CNT, 10' RAT HOLE (OIR)

Remarks: CEMENTED BY HALIBURTON OMA.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed [Signature] (TECHNICIAN) DOIC

FORM CP-2/3 Rev. 9-82

INVOICED

DATE 5-4-83

INV. NO. 4175-W

RECEIVED STATE CORPORATION COMMISSION 4-25-83 APR 25 1983

CONSERVATION DIVISION Wichita, Kansas