

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22005-00-00
Spot: CNESENE Sec/Twnshp/Rge: 36-10S-17W
3630 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: WHISMAN Well Number: 9
County: ROOKS Total Vertical Depth: 3575 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N. MARKET, STE 1130
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 201 w/150 sxs cmt
Production: Size 4.5 feet: 3571 w/250 sxs cmt
Liner: Size feet:

\$116.19

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/03/2001 8:00 AM

Plug Co. License No.: 5042 Plug Co. Name: EDMISTON OIL COMPANY, INC.

Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (316) 265-5241

Proposed Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plugging Bottom plug set at 3000'.
Method: Tubing fish at 1175' - tried to squeeze at 1121'.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/03/2001 10:00 AM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Ran in hole with tubing to 1025'.
Spotted 50 sxs cement with 100# hulls to circulate cement to surface.
P.O.O.H. with tubing and squeezed with 25 sxs cement to Max. P.S.I. 1000#. S.I.P. 1000#.

INVOICED
DATE 03-07-2001
INV. NO. 2001061402

Remarks: ALLIED CEMENTING COMPANY - RUSSELL, KANSAS

RECEIVED
STATE CORPORATION COMMISSION
2-14-01
FEB 14 2001

Plugged through: TBG

District: 04

ND

Signed Dennis L. Hamel
(TECHNICIAN)

STATE CORPORATION COMMISSION
FEB 14 2001

FEB 06 2001

MONTGOMERY DRILLING PROGRAMS

P.O. BOX 1114

HAYS, KS 67601

CONTR MONTGOMERY EXPLORATION, INC CTY

#9 WHISMAN


ROOKS

36-10-17W
NE SE NE

GEOL

FIELD

BRUNGARDT EAST



ELV 1939 KB SPD 4/18/83 CARD ISSUED 9/22/83 IP P 15 BO & 60 BWPD

1934 GL

LKC 3196-3378 OA

API 15-163-22,005

CONG 3420-3440

LOG	Tops	Depth: Datum
ANH		1152+ 787
B/ ANH		1186+ 753
TOP		2866- 927
HEEB		3096-1157
TOR		3118-1179
LANS		3139-1200
BKC		3382-1443
MARM CONG		3410-1471
CONG PAY ZN		3419-1480
SIMP SH		3538-1599
ARB		3558-1619
RTD		3575-1636

8 5/8 " 201 150SX; 4 1/2 " 3571/250SX

NO DST'S

MICT - CO. PF (CONG) 10/ 3420-40, FRAC 8,000# SD & 500 BW,
SWB DWN. SO, SET BP ABOVE CONG PF'S (DEPTH NA), PF (LKC)
3370-78, 3349-59, 3326-30, 3299-3304, 3277-87, 3235-40 &
3196-3201 W:2 SPF, AC 21,000G (28% HYDROCHLORIC ACID) OA
LKC ZNS, SWB DWN. SO, PULLED PLUG, POP, P 15 BO & 60
BWPD, 6/22/83 - COMMINGLED

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS