

4-041860

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-12

API Number: 15-163-21,563-0000

SE NE SE /4 SEC. 13, 10 S, 18 W
1650 feet from S section line
330 feet from E section line

Operator license# 3456

Lease: Ganoung "A" Well # 1

Operator: AFG Energy, Inc.

County: Rocks 122.52

Address: P.O. Box 458
Hays, Kansas 67601

Well total depth 3770 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet
w/ 165 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing, Inc. License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 12 Month: December Year 1996

Plugging proposal received from: Terry W. Piesker

Company: AFG Energy, Inc. Phone: 913-625-6374

Were: 4 1/2" casing set at 3760' w/250 sxs.
Perfs. at 3666' - 3670'. D.V. at 1484' with 500 sxs. PBSD 3690'.
Ordered 300 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:30 P.M., Day: 12, Month: December, Year: 1996

Actual plugging report: Ran tubing 3665' - spotted 100 sxs cement with 350# hulls. Pulled tubing to 1518' - spotted 70 sxs cement to circulate at surface. Pulled tubing and squeezed 4 1/2" casing to 500# with 15 sxs cement S.I.P. 300#.

12-23-96

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugging through TUBING, CASING. Elevation: 2154 K.B.

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE DEC 31 1996

WV. NO. 47187