

4- 041395

7-30
15-163-00580-0001
14
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 6-30-83

OWWO

SW SW NE /4 SEC. 13, 10 S, 18 W
2970 3630 feet from S section line
2310 990 feet from E section line

FT
KCC

Operator license# 3456

Lease Jaco well # 4

Operator: A.F.G. Energy, Inc.

County Rooks

Address: P.O. Box 605
Russell, Kansas 67665

Well total depth 4000 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 211 feet
w/145 sx.

130.00

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 7:30A.M. Day: 30 Month: July Year: 92

Plugging proposal received from: Terry Piesker

Company: A.F.G. Energy, Inc. Phone: 913-483-6213

Were: 4 1/2" casing set @ 3978' w/275 sx. cement. Perf. @ 3518'-3668'.
Anhy. Perf. @ 1528' w/550 sx. W.L.M. 3550'.
Ordered 250 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:00A.M., Day: 30, Month: July, Year: 92

Actual plugging report: Hooked-up 4 1/2" casing. Pumped in 175 sx.
cement with 300# hulls. Max. 700#. S.I. 400#. Hooked-up to 8 5/8"
S.P. Pumped in 75 sx. cement with 1/4# flocele. Max. 400#. S.I. 200#.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
8-12-92

Aug 12 1992

CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

DATE 8-20-92

INV. NO. 35988

NO