

4-041557

1-5 15-163-19409-0005 5 P

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 4-17-59

E2 W2 SE /4 SEC. 16 , 10 S, 18 W
1320 feet from S section line
1650 feet from E section line

Operator license# - Lease Ordway I well # 1

Operator: Kansas Corporation Commission County Rooks

Address: State Fee Fund Plugging Well total depth 3757 feet
2301 E. 13th Street Conductor Pipe: 0 inch @ 0 feet
Hays, Kansas 67601 Surface pipe 8 5/8 Inch @ 164 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 4 Month: January Year: 94

Plugging proposal received from: Dennis L. Hamel

Company: Kansas Corporation Commission Phone: 913-628-1200

Were: 4 1/2" casing set @ 3755' w/N.A.sxs. cement. Perf. @ 3732' - 3735'. Anhy. @ 1480' - Dakota @ 835' - Junk in hole - 1 joint of tubing. Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 6:30P.M., Day: 5, Month: January, Year: 94

Actual plugging report: R.I.H. with tubing to 1488'. Casing bad from 1030' to 1185'. Tubing stacking out - had to be turned and washed down to 1488' (base of anhy.) - appeared to be out of casing. Determined adequate plug could be placed here. Perf. @ 1480' and 835'. Rigged up cementers - pumped 140 sxs. cement to circulate to surface. Pulled tubing. Squeezed casing at surface with 75 sxs. additional cement. Max. 800#. S.I.P. 600#. Hooked-up to 8 5/8" S.P. Squeezed in 35 sxs. cement w/100# hulls. Max. 400#. S.I.P. 400#.

Remarks: Vincent Hrabe Dec. - Operator of record.
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X SNOE CORPORATION COMMISSION
Plugged through TUBING X, CASING . Elevation: GL

I did[X] / did not[] observe the plugging.

RECEIVED
JAN 13 1994
Dennis L. Hamel

HD (agent)
CONSERVATION DIVISION
Wichita, Kansas