

8-14

4-041918

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-22,894-0000

S2 SW NW /4 SEC. 16, 10 S, 18 W
2970 feet from S section line
4650 feet from E section line

Operator license# 5537

Lease: E.C. Ordway "A" Well # 4

Operator: Viola E. Brown
d/b/a Kenny Brown Enterprises
Address: 400 N. Washington
P.O. Drawer 340
Plainville, Kansas 67663

County: Rooks 122.20
Well total depth 3760 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 207 Feet
W/140 sxs cmt.

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Halliburton Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00 A.M. Day: 14 Month: August Year 1997

Plugging proposal received from: Steve Ruder

Company: Kenny Brown Enterprises Phone: -

Were: 5 1/2" casing set at 3755' w/500 EA-2 sxs cement. Perfs at 3356' - 3573'.
Ordered 175 sxs 60/40 pozmix - 10% gel - 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 11:00 A.M., Day: 14, Month: August, Year: 1997

Actual plugging report: Rigged up cementers to 4 1/2" casing. Squeezed casing as follows:
16 sxs cement with 200# hulls, followed with 14 sxs gel, followed with 115 sxs cement. Max.
P.S.I. 450#. S.I.P. 250#. W.A.M. - additional 60 sxs cement to the top.
8 5/8" S.P. Squeezed to Max. P.S.I. 800#.

8-27-97

Remarks:
Condition of casing(in hole): GOOD BAD _____
Bottom plug(in place): YES , CALC _____, NO _____
Plugged through TUBING _____, CASING .
Any plug: YES NO _____
Dakota plug: YES , NO _____
Elevation: _____ G.L. _____

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 8-29-97

INV. NO. 48879