

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01862-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 16-10S-18W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: ORDWAY B Well Number: 2
County: ROOKS Total Vertical Depth: 3566 feet

Operator License No.: 32250
Op Name: KENNY BROWN ENTERPRISES LLC
Address: BOX 277 1602 E. 28TH
HAYS, KS 67601

Production Casing Size: 5.5 feet: 3565 125 SX CMT
Surface Casing Size: 8.625 feet: 288 225 SX CMT

#115 90

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2003 1:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: STEVE RUDER Company: KENNY BROWN ENTERPRISES LL Phone: (785) 650-7031

Proposed: Ordered out 250 sxs SMDC and 500# hulls.
Plugging: No squeeze records. Perforated 1800' - 1575' - 974'.
Method: Fluid 1200' from surface. PBTD 3415'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/06/2003 7:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech perforated Salt 1800'. Anhydrite 1575'. Base Dakota 974'.
Swift pumped 35 sxs SMD down backside.
Max. P.S.I. 600#. S.I.P. 600#.
Hooked up to 5 1/2" casing - pumped 160 sxs SMD with 700# hulls. S.I.P. 0#.
Left set one hour. Cement down 1400'. Shut in 30 minutes and pumped 25 sxs cement 600'.
Shut in two hours.
Topped off with 50 sxs SMD - hole full.

RECEIVED
10-9-03
OCT 09 2003
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

102 Signed Richard Williams
(TECHNICIAN)

INVOICED
DATE 10-9-03
INV. NO. 2004060592

OCT 08 2003

MAGICEE

SUNRAY OIL

#2 ORDWAY

16-10-18W
SW SW NE

Contr. STICKLE DRLG ROOKS County

E. 2149 RB Comm. 4-29-55 Comp. IP 180 BOPD

Tops	Depth	Datum	Casing
HEEB	3328	-1179	8" 288 DST 3407-14/1 HR; 350'
TOR	3349	-1200	5" 3565 OIL, 10' WTR, BHP 540#
LANS	3369	-1220	DST 3426-36/1 HR, 18' OCM; BHP
			70#; DST 3497-3516/1 HR, 80' O
			& GCM, 70' G & MCO, 50' WTR, BHP
			950#; CO 3525; PERF 42/3502-09;
			2 GO & 2 GWPH; ACID 1250; SWB
			8 BO & 3 BW/4 HR; PB 3485; 30/
			3401-06; 18/3406-09; 25 GOPH
			WILLIAMS SE POOL ACID 1250; SWB
ID	3566	-1417	14 BOPH/4 HRS

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS
