

8-14

15-163-00722-0000

4-041917

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - N/A

SE SE NW /4 SEC. 16, 10 S, 18 W
2970 feet from S section line
2970 feet from E section line

Operator license# 5537

Lease: E.C. Ordway "A" Well # 2

Operator: Viola E. Brown
d/b/a Kenny Brown Enterprises
Address: 400 N. Washington
P.O. Drawer 340
Plainville, Kansas 67663

County: Rooks 120.32
Well total depth 3702 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 284 Feet
W/175 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00 A.M. Day: 14 Month: August Year 1997

Plugging proposal received from: Steve Ruder

Company: Kenny Brown Enterprises Phone: -

Were: 5 1/2" casing set at 3699' w/175 sxs cement. Perfs at 3173' - 3456'.
Anhy at 1540' - Salt at 2150' - Dakota at 900' - Pulled tubing.
Ordered 200 sxs mid-con two cement with 1/4# F.C. plus 500# hulls - plus 14 sxs gel.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:30 P.M., Day: 14, Month: August, Year: 1997

Actual plugging report: Squeezed 5 1/2" casing with 16 sxs cement with 200# hulls, followed with 14 sxs gel, followed with 150 sxs cement with 300# hulls. Max. P.S.I. 450#. S.I.P. 350#. 8 5/8" S.P. Squeezed with 20 sxs cement with 100# hulls. Max. P.S.I. 800#. S.I.P. 800#.

7-27-97

Remarks: Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING, CASING X
Anhy.plug: YES X NO
Dakota plug: YES X, NO
Elevation: G.L.

I did[X] / did not[] observe the plugging.

Dennis Hamel
(agent)

Form CP-2/3

INVOICED

DATE 8-29-97

INV. NO. 48880