

11-7

6 041259

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-22,183 - 0000

SE NW NE , SEC. 16 , T 10 S, R 18 W 4E

4290 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5537

Lease Name Ordway Well # 1

Operator: Kenny Brown Enterprises

County Rooks 123.50

Name & Address 400 N. Washington

Well Total Depth 3800 feet

Address Plainville, Ks. 67663

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 259 w/160

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number

Address Hays, Ks.

Company to plug at: Hour: 8:00 AM Day: 7 Month: Nov Year: 19 90

Plugging proposal received from Kenny Brown

(company name) Same (phone)

were: 5 1/2 casing set at 3799 w/150 sks cement: perfs at 3398 to 3578;

Perf anhy at 1590; perf base dakota at 870.

Ordered 350 sks 65/35 poz 10% gel w/1/4 lb f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:20 AM Day: 7 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2 casing w/25 sks cement w/1/4 lb f.c. plus pumped in add 325 sks cement w/1/4 lb f.c. and 500 lbs. hulls mixed in cement. Max 400 lbs. S.I. 300 lbs.

Cement at surf in bradenhead.

RECEIVED
STATE CORPORATION COMMISSION
11-30-90
NOV 30 1990

CONSERVATION DIVISION
Wichita Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 12-6-90

INV. NO. 30163

J.L.S.

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis L. Hamel