

6 040341

15-163-02409-0001

Dulled  
(5-15-1989)

API NUMBER 15-

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NE SW SEC. 16, T. 10 S., R. 18 W. &

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363 RTKLL

Lease Name Ordway Well # C-5

Operator: Davis Brothers

County Rooks 121.23

Name & Address One Williams Ctr.

Well Total Depth 3730 feet

Suite 2000

Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_

Tulsa, OK 74172

Surface Casing: Size 8 5/8 feet 183'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Contg License Number \_\_\_\_\_

Address Hays, Kansas

Company to plug at: Hour: 10:30 Day: 18 Month: 3 Year: 19 85

Plugging proposal received from Chuck Arnold

(company name) Davis Brothers (phone) \_\_\_\_\_

were: 5 1/2" csg set @ 3665' Surf 3514' to 3612'

Operator will run tbg. - Holes in csg @ 859' to 1089'

Ordered 300 sx 60/40 psg 10% gel, 32 sx gel, 10 sx hulls

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 Day: 18 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT

Spotted through tbg: 40 sx cmt w/ 2 sx hulls @ 3600'; 11 sx gel w/ 1 sx hulls @ 3200'; 11 sx gel w/ 1 sx hulls @ 2100' (circ 8.5); 50 sx cmt w/ 1 sx hulls @ 1025'; 50 sx cmt w/ 1 hull @ 500' (circ cmt); pressured up 5 1/2" csg w/ 10 sx. cmt. to 700 # P.S.I.

Impd into 8 5/8" S.P. -> 60 sx cmt, 10 sx gel, 100 sx cmt.

Remarks: P.S.I. 900 #

(If additional description is necessary, use BACK of this form.) 3-25-85

I (did / did not) observe this plugging.

3-26-85

Signed Dennis L. Hamel  
(TECHNICIAN) 3-22-85

INV. NO. 7427

APR 26 1985