

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01861-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 16-10S-18W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: ORDWAY B Well Number: 1
County: ROOKS Total Vertical Depth: 3751 feet

Operator License No.: 32250
Op Name: KENNY BROWN ENTERPRISES LLC
Address: BOX 277 1602 E. 28TH
HAYS, KS 67601

Production Casing Size: 5.5 feet: 3664 120 SX CMT
Surface Casing Size: 8.625 feet: 288 225 SX CMT

\$ 121.9'

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2003 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: STEVE RUDER Company: KENNY BROWN ENTERPRISES LL Phone: (785) 650-7031

Proposed Plugging Method: Ordered out 250 sxs SMDC and 1000# hulls.
Squeeze jobs: 07-04-74 900'-1050' w/350 sxs.
06-03-87 2600' w/150 sxs.
07-10-90 2962' w/250 sxs.
02-05-92 2300'w/150 sxs.
Tubing parted at 1408'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/06/2003 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Fluid level 800'.
Ran tubing to 1400' - top of fish.
Swift Services pumped 140 sxs neat cement.
Pulled tubing to 900' - pumped 35 sxs cement with 300# hulls.
Pulled tubing to 500' - pumped 35 sxs cement with 300# hulls.
Pulled tubing out of hole - squeezed with 35 sxs cement with 400# hulls.
Max. P.S.I. 600#. S.I.P. 350#.
Hooked up to backside - pumped 5 sxs cement. S.I.P. 600#.

RECEIVED
10-9-03
OCT 09 2003
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED
DATE 10-9-03
TEL. NO. 2004060591

Form CP-2/3

OCT 08 2003

SUNRAY OIL

#1 ORDWAY

16-10-18W
NW SW NE

Contr. STICKLE DRILLING

ROOKS

County

E 2170 RB Comm. 5-1-54 Comp. 6-4-54 IP 234 BOPD

Tops	Depth	Datum
TOP	3131	-961
HEEB	3348	-1178
TOR	3363	-1193
LANS	3387	-1217
B/KC	3621	-1451
MARM	3630	-1460
CONG	3650	-1480
SIMP	3705	-1535
ARB	3736	-1566
TD	3751	-1581

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Casing
 8" 288
 5" 3664 DST 3411=36/1 HR, 670'
 H GCO, BHP 990#;
 DST 3470-82/1 HR, 150' G, 360' GCO, 270'
 WTR, BHP 1060#; DST 3747-51/1 HR, 2100'
 WTR, BHP 1095#;
 CO 3550: PERF 42/3520-34: 18 GOPH; ACID
 1750: 30 BO & 30 BWPB: 18/3445-51: 2
 BOPB & 4 GWPH: 15/3422-27: ACID. 750: SWB
 68 BO & 14 BW:

WILLIAM SE POOL
