

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
06-06-66  
JUN - 6 1966  
Conservation Division  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. William Cohen of William Cohen & Co. has this date requested permission to plug the following described well:

Mr. William Cohen guarantees payment of the plugging fee.

Operator's full Name: William Cohen & Co.

Complete Address: 245 Patton, Wichita, Kansas

Lease Name: Woelk Estate Well No. # 1

Location: C SE SE Sec. 28 Twp. 12 Rge. 14 (E) (W) W

County Russell Total Depth 3280 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. R. E. Smith was instructed to plug the well as follows:

- 8 5/8" 302' Cwc.
- Sanded hole back to 3240' & dumped 5 sax cement with dump bailer.
- Pulled pipe. Mudded hole to 300', set rock bridge, displaced 5 sax cement. Let set over night. Bailed hole dry, displaced 20 sax cement. Mud to 40', set rock bridge, & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don Lruan  
Conservation Division Agent