

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 9 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
02-09-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Marvin Mayers of Marvin Mayers has this  
date requested permission to plug the following described well:

Mr. Marvin Mayers guarantees payment of the plugging fee.

Operator's full Name: Marvin Mayers

Complete Address: Box 138, Russell, Kansas 67665

Lease Name: Foster "B" Well No. # 1

Location: NW NE SE Sec. 29 Twp. 12 Rge. 14 (E)(W) W

County: Russell Total Depth 2293 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Ralph Watson was instructed to plug the well as follows:

8 5/8" 686' Cwc.

Sanded hole back to 2240' & dumped 4 sax cement with dump bailer.

Pulled pipe. Mudded hole to 375', set 25' rock bridge, & displaced

5 yds. Ready-mix Cement, cementing from 350' to base of cellar.

Very truly yours,

Don Luman  
Conservation Division Agent