

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Rec'd KCC  
07-07-82

Dear Sir:

Mr. Larry Hinderliter of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Operator's Full Name: Rains & Williamson Oil Co.

Complete Address: 435 Page Court 220 W. Douglas, Wichita, Ks. 67202

Lease Name: Teppe Well No. 1

Location: 750' FNL 410' FWL Sec. 33 Twp. 12 Rge. 14 (E) (W)

County: Russell Total Depth: 3120'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XXX

Other well as hereafter indicated: \_\_\_\_\_

Mr. Hinderliter was instructed to plug the well as follows:

8 5/8"-645' S.P. cuc. w/100 sacks common-2% Gel.-3% Cal.Cl. & 200 sacks

60/40 posmix-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug

spot w/drill stem w/heavy mud between all plugs.

1st plug @ 640' w/70 sacks cement

2nd plug @ 310' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Very truly yours,

[Signature]  
Conservation Division Agent