

State of Kansas



15-167-2113-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
12-19-1977  
DEC 19 1977

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. John Linden of B&N Drlg. Co. has this date requested permission to plug the following described well:

Mr. John Linden guarantees payment of the plugging fee.

Operator's full Name: BMG Inc.

Complete Address: 1400 Metrobank Bldg., Denver, Colo.

Lease Name: McAninch Well No. 1

Location: NW NW SW Sec. 13 Twp. 12 Rge. 15 (E)(W)X

County: Russell Total Depth 2910' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. John Linden was instructed to plug the well as follows:

Fill hole with mud and spot 30 sx cement at 480'.

Fill hole with mud and spot 20 sx cement at 270'.

Fill hole with mud to 40' and 1/2 sx hulls, plug,  
and 10 sx cement.

297' of 7" surface casing cement circ.

Very truly yours,

Donald Rankin  
Conservation Division Agent