



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

RECEIVED
 STATE CORPORATION COMMISSION
 7-15-1963
 JUL 15 1963

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Morris G. Veverka of Morris G. Veverka Oil Co. has this date requested permission to plug the following described well:

Mr. Morris G. Veverka guarantees payment of the plugging fee.

Operator's full Name: Morris G. Veverka Oil Company

Complete Address: Box 181. Plainville, Kansas

Lease Name: Shaffer Well No. # 2

Location: NE NE NW Sec. 21 Twp. 12 Rge. 15W(E) (W)

County Russell Total Depth 3300 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Walter Voth was instructed to plug the well as follows:

8 5/8" 165' Cwc.

Set bottom plug @ 2900' & 5 sax cement with dump bailer.
Circulated hole with mud @ 450'; pulled pipe to 230'; dis-
placed 30 sax cement thru pipe with mud pump. Pulled re-
maining pipe; set rock bridge; displaced 10 sax cement,
 cementing to base of cellar.

Very truly yours,

Lawson
 Conservation Division Agent

INVOICED

DATE 7-15-63

INV. NO. 7408-W