



ROBERT B. DOCKING Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 DALE E. SAFFELS Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 300 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 S-27-1968  
 MAY 27 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. H. M. Johnson of Gabbert-Jones, Inc. has this

date requested permission to plug the following described well:

Mr. O. A. Sutton guarantees payment of the plugging fee.

Operator's full Name: O. A. Sutton

Complete Address: 800 Sutton Place, Wichita, Kansas

Lease Name: Hoff Well No. # 1

Location: SW SW NW Sec. 32 Twp. 12 Rge. 15 (E)(W) W

County: Russell Total Depth 3029 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. H. M. Johnson was instructed to plug the well as follows:

8 5/8" 240' Cwc.

Circulated hole with heavy mud to 550', set plug, & displaced 70 sax

cement thru drill pipe. Mud to 235', set plug, & displaced 25 sax

cement thru drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced

10 sax cement with Halliburton Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don L. [Signature]  
 Conservation Division Agent