

State of Kansas



15-167-20157-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2-12-1968
FEB 12 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Miller of L. J. Dreiling & Sons, Inc. has this
date requested permission to plug the following described well:

Mr. V. Francis Weigel guarantees payment of the plugging fee.

Operator's full Name: V. Francis Weigel

Complete Address: Box 244, Gorham, Kansas

Lease Name: T. Mermis Well No. # 1

Location: NE NE SE Sec. 33 Twp. 12 Rge. 15 (E)(W) W

County: Russell Total Depth 3262 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bob Miller was instructed to plug the well as follows:

8 5/8" 208' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 35 sax

cement thru drill pipe. Mud to 210', set plug, & displaced 25 sax

cement thru drill pipe. Mud to 40', 1/2 sax hulls, & displaced 10 sax

cement with Allied Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Lawrence
Conservation Division Agent