



15-167-20220-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 8-6-1968
 AUG 6 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Clarence Michael of Sage Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Charles W. Akins guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling Inc.

Complete Address: 400 N. Woodlawn, Suite 7, Wichita, Kansas

Lease Name: Mermis Well No. # 1

Location: App. NE SW NE Sec. 33 Twp. 12 Rge. 15 (E)(W) W

County: Russell Total Depth 3262 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Clarence Michael was instructed to plug the well as follows:

8 5/8" 210' Cwc.

Circulated hole with heavy mud to 480', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 200', & displaced 20 sax cement thru

drill pipe. Mud to 40', set plug with 1/2 sax hulls, & displaced 10

sax cement with Globe Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Don Loman
 Conservation Division Agent