

RECEIVED

JAN 24 2006

KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM

WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 5004
Name: Vincent Oil Corporation
Address: 125 N. Market, Suite 1075
City/State/Zip: Wichita, Kansas 67202
Purchaser: none
Operator Contact Person: Rick Hiebsch
Phone: (316) 262-3573
Contractor: Name: Pickrell Drilling Co., Inc.
License: 5123
Wellsite Geologist: Ken LeBlanc

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

11-30-05 12-8-05 12-8-05
Spud Date or Recompletion Date Date Reached TD Completion Date or Recompletion Date

API No. 15 - 047215180000
County: Edwards
SW SW NE NE Sec. 30 Twp. 26 S. R. 16 East West
2310 feet from S / (N) (circle one) Line of Section
2240 feet from (E) W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) (NE) SE NW SW
Lease Name: Wood Well #: 1-30

Field Name: Trousdale West Extension
Producing Formation: none - dry hole
Elevation: Ground: 2094 Kelly Bushing: 2099
Total Depth: 4410 Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 424 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to DH - Dig - 10/14/08 w/ _____ sx cmt.


Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content 22000 ppm Fluid volume 75 bbls
Dewatering method used pull off free fluids and then evaporation
Location of fluid disposal if hauled offsite: _____
Operator Name: Oil Producers, Inc. of Kansas
Lease Name: Palmatier #2 SWD License No.: 8061
Quarter SW Sec. 16 Twp. 25 S. R. 16 East West
County: Edwards Docket No.: D-2093

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Richard H. Dulced
Title: President Date: 1-20-06
Subscribed and sworn to before me this 20th day of January,
2006.

Notary Public: Yolanda Eubanks
Date Commission Expires: _____



KCC Office Use ONLY
NO Letter of Confidentiality Received
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

WOOD #1-30
DRILLING INFORMATION

70' E of SW SW NE
Sec. 30-26S-16W
Edwards County, KS

RECEIVED

Vincent Oil Corporation
Mull East Prospect

JAN 24 2006

KCC WICHITA

OPERATOR: Vincent Oil Corporation

MUD PROPERTIES
Vis. Wt. W.L. Cost

CONTRACTOR: Pickrell Drilling Rig 10

ELEVATION: 2094 ft. G.L.- 2099 K.B.

STRAIGHT HOLE SURVEY

GEOLOGIST: Ken LeBlanc

Degree	Depth
1	429'
1	1425'
1	2763'

REFERENCE WELL: Vincent Oil Corporation
Thompson #6
S/2 NE SW
Sec. 30-26S-16W

SAMPLE TOPS	REF. WELL	ELECTRIC LOG	REF. WELL
-------------	-----------	--------------	-----------

Heebner Shale	3863 (-1764) -5	3864 (-1765)	-6
Brown Lime	4013 (-1914) -7	4011 (-1912)	-5
Lansing	4030 (-1931) -7	4029 (-1930)	-6
Stark Shale	4255 (-2156) -14	NDE	
Pleasanton	4348 (-2249) -16	NDE	
Marmaton	4390 (-2291)	NDE	
RTD	4410 (-2311)	4066 (-1967)	

11-30-05 Moved in drilling rig and rigged up. Spud at 11:30 pm.

12-01-05 Drilled 12¼ in. hole to 429 ft. KB. Ran 8 5/8 24# surface casing and set at 424 ft. Allied cemented with 450 sacks of 60-40 poz-mix, 2% gel, 3% CC. Plug down at 11:30 AM. Cement did circulate.

12-02-05 Drilling at 932 ft.

12-03-05 Drilling at 2014 ft.

12-04-05 Drilling at 2680 ft.

12-05-05 Drilling at 3271 ft.

12-06-05 Drilling at 3846 ft.

12-07-05 Drilled to 4360 ft. DST #1 4325 to 4360 ft. (Pleasanton)
30", 60", 30", 60"
1st open: no blow
2nd open: no blow, flushed tool and still no blow
Rec'd: 15' of mud
IFP: 16# - 17# ISIP: 18#
FFP: 19# - 19# FSIP: 27#
Zone is non-commercial

WOOD #1-30
DRILLING INFORMATION

Page 2 of 2

RECEIVED

JAN 24 2006

KCC WICHITA

12-08-05

Drilled to total depth of 4410 ft. Due to problems with hole could not get electric log below about 4050 ft. Decided not to go back and recondition hole as DST over Pleasanton was valid. Logged from 4066 ft. up. **Dry Hole.** Plugged and abandoned as follows: 50sx @ 1100', 50sx @ 450', 20sx @ 60', 15sx in RH of 60-40 poz, 6% gel. Plug down @ 4:10 AM on 12-9-05. Released rig.

ALLIED CEMENTING CO., INC.

KCC 22838

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
MEDICINE LODGE

DATE <u>12-8-05</u>	SEC. <u>30</u>	TWP. <u>26 S</u>	RANGE <u>16 W</u>	CALLED OUT <u>8:30 pm</u>	ON LOCATION <u>1:00 pm</u>	JOB START <u>2:30 am</u>	JOB FINISH <u>4:10 am</u>
LEASE <u>WOOD</u>	WELL # <u>1-30</u>	LOCATION <u>HAWLAND, N TO CO. LINE, 1/2 N</u>			COUNTY <u>EDWARDS</u>	STATE <u>KS</u>	
<u>OLD</u> OR NEW (Circle one)			<u>W/INTO</u>				

CONTRACTOR PICKRELL
 TYPE OF JOB ROTARY PLUG
 HOLE SIZE 7 7/8" T.D. 1100'
 CASING SIZE _____ DEPTH _____
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE 4 1/2" DEPTH 1,100'
 TOOL _____ DEPTH _____
 PRES. MAX 200 MINIMUM 50
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT FRESH WATER

OWNER VINCENT OIL
 CEMENT
 AMOUNT ORDERED 135 sk 60:40:6% GEL

EQUIPMENT
 PUMP TRUCK CEMENTER BILL M.
 # 368 HELPER DWAYNE W.
 BULK TRUCK
 # 364 DRIVER THOMAS D.
 BULK TRUCK
 # _____ DRIVER _____

COMMON	<u>81</u>	<u>A</u>	@	<u>8.70</u>	<u>704.70</u>
POZMIX	<u>54</u>		@	<u>4.70</u>	<u>253.80</u>
GEL	<u>7</u>		@	<u>14.00</u>	<u>98.00</u>
CHLORIDE			@		
ASC			@		
			@		
			@		
			@		
			@		
			@		
			@		
HANDLING	<u>142</u>		@	<u>1.60</u>	<u>227.20</u>
MILEAGE	<u>30 x 142 x .06</u>				<u>255.60</u>
					TOTAL <u>1539.30</u>

RECEIVED
 JAN 24 2006
 KCC WICHITA

REMARKS:

1st PLUG 1,100', LWD HOLE, MIX 50 SK 60:40:6% GEL, DISPLACE WITH FRESH WATER, 2nd PLUG 450', MIX 50 SK 60:40:6% GEL, DISPLACE WITH FRESH WATER, 3rd PLUG 60', MIX 20 SK 60:40:6% GEL, PLUG METHOD WITH 15 SK 60:40:6% GEL, WASH UP, RIG DOWN.

SERVICE

DEPTH OF JOB	<u>1,100'</u>			
PUMP TRUCK CHARGE				<u>665.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>30</u>	@	<u>5.00</u>	<u>150.00</u>
MANIFOLD		@		
		@		
		@		
TOTAL <u>815.00</u>				

CHARGE TO: VINCENT OIL
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		
TOTAL _____			

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX
 WILL BE CHARGED
 UPON INVOICING

TAX _____
 TOTAL CHARGE [scribble]
 DISCOUNT [scribble] IF PAID IN 30 DAYS

SIGNATURE Mike Kern

Mike Kern
 PRINTED NAME

ALLIED CEMENTING CO., INC.

22853

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Med. Line LDG.

DATE <u>12-1-05</u>	SEC. <u>30</u>	TWP. <u>26S</u>	RANGE <u>16W</u>	CALLED OUT <u>1:00AM</u>	ON LOCATION <u>11:00AM</u>	JOB START <u>11:00AM</u>	JOB FINISH <u>11:30AM</u>
LEASE <u>Wood</u>	WELL # <u>1-30</u>	LOCATION <u>Haviland N, To Co.</u>			COUNTY <u>Edwards</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)		LINE <u>1 1/2 N W/INTO</u>					

CONTRACTOR Pickrell
 TYPE OF JOB Surface
 HOLE SIZE 12 1/4 T.D. 429
 CASING SIZE 8 5/8 DEPTH 429
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE 4 1/2 DEPTH 429
 TOOL _____ DEPTH _____
 PRES. MAX 250 PSI MINIMUM —
 MEAS. LINE _____ SHOE JOINT 15 FT
 CEMENT LEFT IN CSG. 15 FT
 PERFS. _____
 DISPLACEMENT Fresh Water 26 BBLs

EQUIPMENT

PUMP TRUCK CEMENTER David W.
 # 343 HELPER Dennis C.
 BULK TRUCK
 # 363 DRIVER Larry F.
 BULK TRUCK
 # _____ DRIVER _____

REMARKS:
Pipe on Bottom Break C.M. Pump
450SX 60'40'2+3% CC shot
Down Release Plug Displace
w/26 BBLs Fresh water
shot in wash up Rig Down.

CHARGE TO: Vincent Oil Corp.
~~_____~~
 STREET _____
 CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

SIGNATURE x Mike Kern

OWNER Pickrell Drilling
 CEMENT
 AMOUNT ORDERED 450SX 60'40'2+3% CC

COMMON	<u>270</u>	<u>A</u>	@	<u>8.70</u>	<u>2349.6</u>
POZMIX	<u>180</u>		@	<u>4.70</u>	<u>846.0</u>
GEL	<u>8</u>		@	<u>14.00</u>	<u>112.00</u>
CHLORIDE	<u>15</u>		@	<u>38.00</u>	<u>570.00</u>
ASC			@		

RECEIVED
 @
JAN 24 2006
 @
KCC WICHITA
 @
 HANDLING 473 @ 1.60 756.80
 MILEAGE 30 x 473 x .06 851.40
 TOTAL 5485.0

SERVICE

DEPTH OF JOB	<u>429'</u>			
PUMP TRUCK CHARGE	<u>0-300'</u>			<u>670.00</u>
EXTRA FOOTAGE	<u>129'</u>	@	<u>.55</u>	<u>70.95</u>
MILEAGE	<u>30</u>	@	<u>5.00</u>	<u>150.00</u>
MANIFOLD	<u>Head Rent</u>	@	<u>75.00</u>	<u>75.00</u>

TOTAL 965.95

8 5/8' PLUG & FLOAT EQUIPMENT

1-RUBBER Plug	@	<u>100.00</u>	<u>100.00</u>
	@		
	@		
	@		
	@		

TOTAL 100.00

TAX _____
 TOTAL CHARGE ~~_____~~
 DISCOUNT ~~_____~~ IF PAID IN 30 DAY

x Mike Kern
 PRINTED NAME