

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form AGO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 05317
Name: Continental Energy
Address: P.O. Box 918
City/State/Zip: Garden City, KS 67846
Purchaser: Unimark
Operator Contact Person: Russell Freeman
Phone: (620) 276-8710
Contractor Name: Border Line, Inc.
License: _____

Wellsite Geologist: None
Designate Type of Completion:
 New Well _____ Re-Entry _____ Workover _____
 Oil _____ SWD _____ SIOW _____ Temp. Abd. _____
 Gas _____ ENHR SIGW _____
 Dry _____ Other (Core, WSW, Expl., Cathodic, etc) _____

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
_____ Deepening _____ Re-perf. _____ Conv. to Enhr./SWD _____
_____ Plug Back 2979' _____ Plug Back Total Depth _____
_____ Commingled _____ Docket No. _____
_____ Dual Completion _____ Docket No. _____
_____ Other (SWD or Enhr.?) _____ Docket No. _____

11-25-05 _____ 11-26-05 _____ 2-27-06 _____
Spud Date or _____ Date Reached TD _____ Completion Date or _____
Recompletion Date _____ Recompletion Date _____

API No. 15 - 055-21891-00-00
County: Finney
NE SE SW SW
S/2 - S/4 - S/W Sec. 26 Twp 25 (S) R. 33 East West
_____ 625 feet from (S) / N (circle one) Line of Section
_____ 1250 feet from E / W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW (SW)

Lease Name: Kidd Well #: 1-26
Field Name: Panoma
Producing Formation: Council Grove
Elevation: Ground: 2904 Kelly Bushing: 6'
Total Depth: 3020 Plug Back Total Depth: 2979
Amount of Surface Pipe Set and Cemented at _____ 615 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____ 3020
feet depth to Surface w/ 350 _____ sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content 6000 ppm Fluid volume 750 bbls
Dewatering method used evaporation
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ **KCC WICHITA** West
County: _____ Docket No.: _____

RECEIVED
MAR 26 2006

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Russell Freeman
Title: Owner Date: 3-3-06
Subscribed and sworn to before me this 3 day of march
06
Notary Public: Karen Boomer
Date Commission Expires: 10-11-08

KCC Office Use ONLY
_____ Letter of Confidentiality Received
If Denied, Yes Date: _____
_____ Wireline Log Received
_____ Geologist Report Received
_____ UIC Distribution

NOTARY PUBLIC - State of Kansas
KAREN BOOMER
My Exp. _____

Side Two

Operator Name: Continental Energy Lease Name: Kidd Well #: 1-26
 Sec. 26 Twp. 25 S. R. 33 East West County: Finney

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:
 Cement Bond Log
 Gamma Ray Neutron

Log Formation (Top), Depth and Datum Sample

Name	Top	Datum
Council Grove	2860	+44

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8"	23#	615	Com	150	3% cc
						200	Lite 3% cc 1/2 Flo-seal
Prod	7 7/8	5 1/2	14#	3016		150	c
						275	Lite 1/2 Flo-seal

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

RECEIVED
MAR 6 2006

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement & Other Material Used (Amount and Kind of Material Used)	Depth
2	2924-2932	63000# 12/20 Sand	
2	2922-2916	90000# Resin coated 16/30	
3	2900-2890		
3	2870-2860	1500 Gal 15% MCA	

TUBING RECORD	Size	Set At	Packer At	Liner Run
	2 3/8	2950		<input type="checkbox"/> Yes <input type="checkbox"/> No

Date of First, Resumed Production, SWD or Enhr. SI Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours
 Oil Bbls. SI Gas Mct Water Bbls. Gas-Oil Ratio Gravity

Disposition of Gas SI METHOD OF COMPLETION Production Interval 2860-2932

Ventd Sold Used on Lease (If vented, Submit ACO-1H.) Open Hole Perf. Dually Comp. Commingled Other (Specify)

ALLIED CEMENTING CO., INC. 21761

Federal Tax I.D.# /

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLEY

DATE <u>11-26-05</u>	SEC. <u>26</u>	TWP. <u>25S</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>1130 PM</u>	JOB START <u>330 AM</u>	JOB FINISH <u>4:30 AM</u>
LEASE <u>Kidd</u>	WELL# <u>1-26</u>	LOCATION <u>GARDEN CITY 85-3W-S 2A</u>			COUNTY <u>FINNEY</u>	STATE <u>KS</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR CHEYENNE DRILL RIG #11 OWNER SAME
 TYPE OF JOB PRODUCTION STRING
 HOLE SIZE 7 7/8" T.D. 3020'
 CASING SIZE 5 1/2" DEPTH 3016'
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT 26.93'
 CEMENT LEFT IN CSG. 26.93'
 PERFS. _____
 DISPLACEMENT 73 ~~DBL~~

EQUIPMENT

PUMP TRUCK # <u>191</u>	CEMENTER <u>TERRY</u>
	HELPER <u>WAYNE</u>
BULK TRUCK # <u>218</u>	DRIVER <u>LONNIE</u>
BULK TRUCK # <u>386</u>	DRIVER <u>KELLY</u>

REMARKS:
MIX 275 SKS LITE 1/4" FLO-SEAL
150 SKS CLASS "C". WASH TRUCK + LINES
DISPLACE 7 1/4 BBL. WATER.
CEMENT OLD CIRC.
LANDED PLUG AT 1500 ASFL.
FLOAT HELD
LOST RETURN WITH 6 BBL LEFT
TO PUMP

THANK YOU

CHARGE TO: CONTINENTAL ENERGY
 STREET _____
 CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Noel Perez

CEMENT		
AMOUNT ORDERED	<u>150 SKS CLASS "C"</u>	
	<u>275 SKS LITE 1/4" FLO-SEAL</u>	
COMMON	@	
POZMIX	@	
GEL	@	
CHLORIDE	@	
ASC	@	
<u>CLASS "C" 150 SKS</u>	@ <u>12.95</u>	<u>1807.50</u>
<u>LITE 275 SKS</u>	@ <u>8.80</u>	<u>2420.00</u>
<u>FLO-SEAL 69#</u>	@ <u>1.70</u>	<u>117.30</u>
HANDLING <u>445</u>	@ <u>1.60</u>	<u>712.00</u>
MILEAGE <u>64 PER SK / MILE</u>		<u>1335.00</u>
TOTAL		<u>6391.80</u>

SERVICE

DEPTH OF JOB	<u>3016'</u>	
PUMP TRUCK CHARGE		<u>1320.00</u>
EXTRA FOOTAGE	@	
MILEAGE	<u>50 MI</u> @ <u>5.00</u>	<u>250.00</u>
MANIFOLD	@	
TOTAL		<u>1570.00</u>

KCC WICHITA
 5 1/2 PLUG & FLOAT EQUIPMENT

<u>1-AFU FLOAT SHOL</u>		<u>263.00</u>
<u>8-CENTRALIZERS</u>	@ <u>50.00</u>	<u>400.00</u>
<u>1-BASKET</u>	@	<u>140.00</u>
<u>1-LATCH DOWN PLUG ASSY</u>	@	<u>350.00</u>
TOTAL		<u>1153.00</u>

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS
 PRINTED NAME Noel Perez

ALLIED CEMENTING CO., INC.

2721

Federal Tax I.D.#

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

~~Medicine Lake~~
OAKLEY

DATE <u>11-25-05</u>	SEC. <u>26</u>	TWP. <u>25</u>	RANGE <u>33</u>	CALLED OUT	ON LOCATION <u>6:30pm</u>	JOB START <u>7:00pm</u>	JOB FINISH <u>8:00pm</u>
LEASE <u>Ridd</u>	WELL# <u>1-26</u>	LOCATION <u>Garden City S - Ferris</u>	COUNTY <u>Finney</u>	STATE <u>KS</u>			
OLD OR NEW (Circle one) <u>NEW</u>				<u>Sign 30-345 E in</u>			

CONTRACTOR Cheyenne Dals #11 OWNER Zame

TYPE OF JOB Surface

HOLE SIZE 12"4 T.D. 615'

CASING SIZE 8 5/8 23# DEPTH 615'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX. MINIMUM

MEAS. LINE SHOE JOINT 1'

CEMENT LEFT IN CSG. 1'

PERFS.

DISPLACEMENT 39.1 BBL

EQUIPMENT

PUMP TRUCK CEMENTER Ruzzo

343 HELPER Dennis

BULK TRUCK

347 DRIVER Larry

BULK TRUCK

DRIVER

REMARKS:

Cement did circulate

Plus down @ 7:45pm

Thanks

Ruzzo & crew

CHARGE TO: Continental Energy (As per b.d.)

STREET

CITY STATE ZIP

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Leopoldo Perez

PRINTED NAME

CEMENT

AMOUNT ORDERED 150 com 39cc

200 Lite 39cc 114# flo seal

COMMON 150 @ 10⁰⁰ 1500⁰⁰

POZMIX @

GEL @

CHLORIDE 12 @ 38⁰⁰ 456⁰⁰

ASC @

Lite 200 @ 9³⁵ 1870⁰⁰

@

flo seal 50 @ 1⁷⁰ 85⁰⁰

@

@

@

@

@

@

@

@

HANDLING 374 @ 1⁶⁰ 598⁴⁰

MILEAGE .0645K x mile 1122⁰⁰

TOTAL 5631⁴⁰

SERVICE

DEPTH OF JOB 615'

PUMP TRUCK CHARGE 670

EXTRA FOOTAGE @

MILEAGE 50 @ 5⁰⁰ 250

MANIFOLD @

@

@

@

TOTAL 920⁰⁰

PLUG & FLOAT EQUIPMENT

1- 8 1/8 plug @ 1⁰⁰ 1⁰⁰

2- 8 1/8 cent @ 55⁰⁰ 110⁰⁰

1- Bore plate @ 45⁰⁰ 45⁰⁰

@

RECEIVED

MAR 06 2006

TOTAL 210⁰⁰

TAX KCC WICHITA

TOTAL CHARGE

DISCOUNT IF PAID IN 30 DAYS