

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-167-22975-00-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

API NUMBER 15-167-22,975

LEASE NAME C.J. Steckel

WELL NUMBER 1

4,290 Ft. from S Section Line

2,970 Ft. from E Section Line

SEC. 24 TWP. 12 RGE. 15 (E) or (W)

COUNTY Russell

Date Well Completed 6-25-91

Plugging Commenced 6-25-91

Plugging Completed 6-25-91

LEASE OPERATOR Russell Oil, Inc.

ADDRESS PO Box 272, Russell, KS. 67665

PHONE#(913) 483-3954 OPERATORS LICENSE NO. 3,293

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 25, 1991 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,042'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	218'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Fill hole w/heavy mud. Push bridge plug to 900', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 660', spot 90 sax cement on plug thru drill pipe. Push bridge plug to 270', spot 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RUSSELL OIL, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas.

(Employee of Contractor or Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec.-Treas.

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 9th day of July, 1991

Ruth Phillips
Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION

7-10-1991
JUL 10 1991

CONSERVATION DIVISION
Wichita, Kansas


Shields

Russell, Kansas

WELL LOG

Operator: RUSSELL OIL, INC.
 Well: C.J. Steckel #1
 Commenced: June 19, 1991
 Completed: June 25, 1991
 Contractor: Shields Drilling Co.

Well Description: SE NE NW
 Sec. 24-12S-15W
 Russell County, KS.



CASING RECORD

Size	Run	Pulled
8 5/8"	218'	Cmtd. w/150 sax

Elevation: 1,811' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand	30'
Lime	40'
Post rock	70'
Shale & lime	221'
Shale	450'
Shale & sand	874'
Anhydrite	911'
Shale	1,325'
Shale & lime	2,744'
Lime	3,042' RTD

Notes