

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

JUN 02 2009 RECEIVED Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Oil Producers of Kansas, Inc. Address: 1710 Waterfront Parkway Phone: (316) 215-1357 Operator License #: 8061 Type of Well: Oil Gas KCCPKT CP213 Docket #: (If SWD or ENHR) The plugging proposal was approved on: by: Steve Durrant (KCC District Agent's Name) Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Mississippi Depth to Top: 4728 Bottom: 4740 T.D.

API Number: 15-N/A 097-20273-0001 Lease Name: McElwain O WWO Well Number: 1 Spot Location (QQQQ): - C - NW - NE 4620 Feet from North / South Section Line 3630 Feet from East / West Section Line 1900 Sec. 6 Twp. 28 S. R. 17 East West County: Kiowa Date Well Completed: 05/15/09 Plugging Commenced: 05/19/09 Plugging Completed: 05/19/09

Show depth and thickness of all water, oil and gas formations.


Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes casing data: 8 5/8" (415'), 4 1/2" (4805', 2270').

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. Sanded off bottom, loaded hole with water, sand was at 4670', bailed 4 sacks cement with bailer, pulled slips, ripped casing at 2430', ripped casing at 2270', pulled casing up to 1130', swedge in, pumped 15 gel, 50 sacks, 100# hulls at 1130', pulled to 445', pumped 50 sacks, 100# hulls, pulled to 40', pumped 20 sacks to surface.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925 Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Oil Producers of Kansas, Inc. State of Kansas County, Sedgwick, ss.

Oil Producers Inc. of Kansas (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature] (Address) 1710 waterfront Parkway Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 1st day of June 20 09. Lori A. Zehr My Commission Expires: May 5, 2010