

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION JUN 02 2009 WELL PLUGGING RECORD RECEIVED K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Oil Producers of Kansas, Inc. Address: 1710 Waterfront Parkway Phone: (316) 680-0231 Operator License #: 8061 Type of Well: Oil Docket #: The plugging proposal was approved on: by: Steve Durrant Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Mississippi Depth to Top: 4556 Bottom: 4576 T.D. Kinderhook Depth to Top: 4612 Bottom: 4617 T.D.

API Number: 15-097-21,505-00-00 Lease Name: Clark Well Number: 1 Spot Location (QQQQ): - NW - NW - NE 4950 Feet from North / South Section Line 2310 Feet from East / West Section Line Sec. 21 Twp. 27 S. R. 16 East West County: Kiowa Date Well Completed: 03/24/03 Plugging Commenced: 05/13/09 Plugging Completed: 05/14/09

Show depth and thickness of all water, oil and gas formations.


Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Contains data for casing records including sizes like 8 5/8" and 4 1/2", 10.5# and depths like 4697' and 2350'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. Sanded off bottom, loaded hole with water, dug cellar, sand was at 4490', bailed 4 sacks cement with bailer, pulled slips, had 18" stretch, cut surface off 4' below ground, ripped casing at 2460', ripped casing at 2350', pulled casing up to 1100', pumped 15 gel, 50 sacks, 100# hulls, pulled to 430', pumped 50 sacks, 100# hulls, pulled to 40', pumped 20 sacks to surface.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925 Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Oil Producers of Kansas, Inc. State of Kansas County, Sedgwick, ss.

Oil Producers Inc. of Kansas (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature] (Address) 1710 Waterfront Parkway, Wichita KS 67206

SUBSCRIBED and SWORN TO before me this 15th day of June, 2009. [Signature] My Commission Expires: May 5, 2010