

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32639
Name: CORAL PRODUCTION CORP.
Address 1: 1600 STOUT ST.
Address 2: SUITE 1500
City: DENVER State: CO Zip: 80202 + 3133
Contact Person: JAMES WEBER
Phone: (303) 623-3573
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
TOPEKA Depth to Top: 3138' Bottom: 3178' T.D. _____
PLATTSMOUTH Depth to Top: 3340' Bottom: 3350' T.D. _____
LANSING Depth to Top: 3488' Bottom: 3492' T.D. 3738

API No. 15 - 051-25335-00-00
Spot Description: SE 1/4 SW 1/4
~~9/2 - S/2 - N/2 - S/2~~ Sec. 7 Twp. 12 S. R. 17 East West
1830/1489 Feet from North / South Line of Section
2550/2823 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: ELLIS
Lease Name: SEIB Well #: 1
Date Well Completed: 11/4/04
The plugging proposal was approved on: 4/21/09 (Date)
by: RICHARD WILLIAMS (KCC District Agent's Name)
Plugging Commenced: 4/21/09
Plugging Completed: 4/21/09

Handwritten notes:
KCC
1/27/09
CPS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
TOPEKA 3163-78'	OIL	SURFACE	8 5/8"	275'	NONE
PLATTSMOUTH 3340-50'	OIL	PRODUCTION	5 1/2"	3738'	NONE
LANSING 3488-92'	OIL				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

60 sks 60/40 pozmix, 4% gel with 200# hulls followed by 15 sks gel & 300# hulls; pumped 185 sks 60/40 pozmix, 4% gel; max PSI - 400#; SIP 50#; 5 sks cement down backside; CIBP @ 3680'

RECEIVED
JUN 01 2009

Plugging Contractor License #: 31925 Name: QUALITY WELL SERVICE INC
Address 1: 190 US HIGHWAY 56 Address 2: _____
City: ELLINWOOD State: KS Zip: 67526 + _____
Phone: (785) 483-2025
Name of Party Responsible for Plugging Fees: CORAL PRODUCTION CORP.
State of COLORADO County, DENVER, ss. _____
JAMES R. WEBER Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: J.R. Weber

Handwritten initials: JRT