


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-167-04512-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Russell County. Sec. 32 Twp. 12 Rge. 15 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Fred J. Haynes
Lease Name McKune Well No. 1
Office Address Bldg. & Loan Bldg., Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed October 28 19 58
Application for plugging filed " " 19 "
Application for plugging approved " " 19 "
Plugging commenced " " 19 "
Plugging completed " " 19 "
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	211'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 200 feet to 40 feet for each plug set.

Fill hole with heavy mud to 200', set plug and cement with 1/2 sack hulls and 20 sacks cement, fill hole with heavy mud to 40', set plug and cement with 1/2 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
11-13-1958
YJV 13 238

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Haynes Drilling Company
Address Bldg. & Loan Bldg., Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Fred J. Haynes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Fred J. Haynes
Bldg. & Loan Bldg., Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of November, 19 58

Reesh L. Schulte
Notary Public.

My commission expires January 17, 1961.

PLUGGING
FILE SEC 32 T. 12 R. 15W
BOOK PAGE 143 LINE 36

15-167-04512-00-00

DRILLERS LOG
NE NE NE 32-12-15
Russell County, Kansas
McKune # 1

Commenced: October 20, 1958

Casing: 8 5/8" at 211'w/135sks

Completed: October 28, 1958

I. P. - D & A

FORMATION:

Clay & Post Rock	55
Shale	211
Red Bed & Shale	515
Sand	550
Red Bed	770
Red Bed & Shale	896
Anhydrite	896-938
Shale	1150
Shale & Shells	1340
Salt & Shale	1450
Shale	1563
Broken Lime & Shale	1750
Shale & Lime	1910
Lime	2010
Shale & Lime	2475
Shale & Lime Streaks	2630
Shale & Lime	2825
Lime & Shale	3000
KO Lime	3013
Conglomerate	3300
TD	3300

RECEIVED
STATE CORPORATION COMMISSION
11-13-1958
NOV 13 1958

CONSERVATION DIVISION

I hereby certify that the above is true and
Correct to the best of my knowledge.

L. J. Drilling Company
Joseph L. Drilling

PLUGGING

FILE SEC 32 T 12 R 15W
BOOK PAGE 143 LINE 36