


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Russell County. Sec. 34 Twp. 12 Rge. (E) 15 (W)
Location as "NE/CNW&SW" or footage from lines SW/SW/NE
Lease Owner Solar Oil Company
Lease Name Davis Well No. 1
Office Address Union National Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-19 1958
Application for plugging filed 7-19 1958
Application for plugging approved 7-19 1958
Plugging commenced 7-19 1958
Plugging completed 7-19 1958
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truar
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	860'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled Hole with heavy mud and set bottom plug at 350' with 25 sacks cement. Filled Hole to 40' with heavy mud and set top plug with 1/2 sacks hulls and 10 sacks cement. Filled to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company
Address 915 Union Center

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. Fred Hambright (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Fred Hambright
915 Union Center (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1958

My commission expires August 20, 1960

A. R. Derrington Notary Public.

PLUGGING
FILE SEC 34 T. 12 R. 15W
BOOK PAGE 110 LINE 9


RECEIVED
STATE CORPORATION COMMISSION
7-29-1958
JUL 29 1958
CONSERVATION DIVISION
Wichita, Kansas

15-167-00332-00-00
WELL LOG

COMPANY **Solar Oil Company**
FARM **Davis** NO. **1**

SEC. **34** T. **12S** R. **15W**
LOC. **SW/SW/NE**

TOTAL DEPTH **3286**
COMM. **7-8-58** COMP. **7-19-58**
SHOT OR TREATED
CONTRACTOR **Lewis Drilling Company**
ISSUED



CASING

20	10
15	8 5/8"-860'
12	6
13	5

ELEVATION **1772 K. B.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Geologic Tops

0 - 40	Post Rock & Shale	Anhydrite	849
40 - 70	Post Rock & sand	Tarkio	2406
70 - 420	Shale	Topeka	2681
420 - 460	Sand & shale	Heebner	2899
460 - 510	Shale & red beds	Toronto	2918
510 - 560	Sand & Pyrite	Lans/KC	2951
560 - 849	Red bed & shale	Conglomerate zone	3228
849 - 883	Anhydrite	Arbuckle	3240
883 - 1055	Red beds & shale		
1055 - 1810	Shale & lime		
1810 - 1933	Lime		
1933 - 2640	Shale & lime		
2640 - 2715	Lime		
2715 - 2780	Lime & shale		
2780 - 2880	Lime		
2880 - 3075	Lime & shale		
3075 - 3160	Lime		
3160 - 3246	Lime & shale		
3246 - 3286	Lime		
3286	Total Depth		

RECEIVED
OIL AND GAS COMMISSION
7-29-1958

PLUGGING
FILE SEC. 34 T. 12 R. 15W
BOOK PAGE 118 LINE 9

State of Kansas
County of Sedgwick } ss:

I, J. Fred Hambright of the Lewis Drilling Company
upon oath state that the above and foregoing is a true and correct copy of the log of the Davis #1 well.

Subscribed and sworn to before me this 24th day of July 19 58

My Commission Expires: August 20, 1960

J. Fred Hambright

A. R. Derrington
NOTARY PUBLIC (A. R. Derrington)