

ORIGINAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 33344
Name: Quest Cherokee, LLC
Address: 211 W. 14th Street
City/State/Zip: Chanute, KS 66720
Purchaser: Bluestem Pipeline, LLC
Operator Contact Person: Jennifer R. Ammann
Phone: (620) 431-9500
Contractor: Name: TXD
License: 33837
Wellsite Geologist: Ken Recoy

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

3/11/07	3/12/07	3/13/07
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 133-26814-00-00
County: Neosho
_____ ne _____ sw Sec. 11 Twp. 30 S. R. 19 East West
1980 feet from (S) N (circle one) Line of Section
1980 feet from E (W) (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW (SW)
Lease Name: Beachner Bros Inc Well #: 11-30-19-2
Field Name: Cherokee Basin CBM

Producing Formation: multiple
Elevation: Ground: 983 Kelly Bushing: n/a
Total Depth: 991 Plug Back Total Depth: 954.12
Amount of Surface Pipe Set and Cemented at 21 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from 954.12
feet depth to Surface w/ 118 sx cmt.

CONFIDENTIAL

Drilling Fluid Management Plan ACT II w/wh
(Data must be collected from the Reserve Pit) 7-16-07
Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Jennifer R. Ammann
Title: New Well Development Coordinator Date: 7/10/07
Subscribed and sworn to before me this 10th day of June,
2007.
Notary Public: Denise V. Vennemman
Date Commission Expires: _____

DENISE V. VENNEMAN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 7-1-08

KCC Office Use ONLY
 Letter of Confidentiality Received
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution
RECEIVED
KANSAS CORPORATION COMMISSION
JUL 11 2007

CONSERVATION DIVISION
WICHITA, KS

Operator Name: Quest Cherokee, LLC Lease Name: Beachner Bros Inc Well #: 11-30-19-2
 Sec. 11 Twp. 30 S. R. 19 East West County: Neosho

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:

Compensated Density Neutron Log
 Dual Induction Log
 Gamma Ray Neutron Log

Log Formation (Top), Depth and Datum Sample

Name Top Datum
 See attached

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4	8-5/8"	22	21	"A"	5	
Production	6-3/4	4-1/2	10.5	954.12	"A"	118	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth:
4	881-884/829-831	300gal 15%HCLw/ 26 bbbls 2%KCl water, 415bbbls water w/ 2% KCL, Biocide, 7900# 20/40 sand	881-884/829-831
4	611-613/629-630/581-584/555-557	300gal 15%HCLw/ 34 bbbls 2%KCl water, 486bbbls water w/ 2% KCL, Biocide, 9300# 20/40 sand	611-613/629-630 581-584/555-557
4	463-467/452-456	300gal 15%HCLw/ 39 bbbls 2%KCl water, 537bbbls water w/ 2% KCL, Biocide, 10600# 20/40 sand	463-467/452-456

TUBING RECORD	Size	Set At	Packer At	Liner Run
	2-3/8"	923	n/a	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No

Date of First, Resumerd Production, SWD or Enhr.	Producing Method
4/28/07	<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	n/a	21.4mcf	37.1bbls		

Disposition of Gas Vented Sold Used on Lease (If vented, Submit ACO-18.)

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval _____

QUEST

Resource Corporation

211 W. 14TH STREET,
CHANUTE, KS 66720
620-431-9500

TICKET NUMBER 2077

FIELD TICKET REF#

FOREMAN Joe

620100

TREATMENT REPORT & FIELD TICKET CEMENT

DATE	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
3-13-07	Beachner Bros INC. 11-30-19-2	11	30	19	NO

FOREMAN / OPERATOR	TIME IN	TIME OUT	LESS LUNCH	TRUCK #	TRAILER #	TRUCK HOURS	EMPLOYEE SIGNATURE
Joe B	7:00	10:00		903427		3	<i>Joe Perm</i>
Paul H	7:00			903197		3	<i>Paul H</i>
Russell A	7:00			903103		3	<i>RA</i>
Gary C	7:00			931500		3	<i>GC</i>
Tyler G	7:00			903142	932452	3	<i>TG</i>

JOB TYPE Longstring HOLE SIZE 6 3/4 HOLE DEPTH 990.90 CASING SIZE & WEIGHT 4 1/2 10.5
 CASING DEPTH 954.12 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 14.5 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 0
 DISPLACEMENT 15.21 DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS:

Installed cement head Ran 2 SKS gel + 9 bbl dyed + 118 SKS of cement
 To get dye to surface. flush pump. Pump wiper plug to bottom + set float
 shoe

954.12	ft 4 1/2 casing
5	Controlizer
1	4 1/2 float shoe

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION OF SERVICES OR PRODUCT	TOTAL AMOUNT
903427	3 hr	Foreman Pickup	
903197	3 hr	Cement Pump Truck	
903103	3 hr	Bulk Truck	
1104	112 SK	Portland Cement	
1124	2	50/50-POZ Blend Cement Baffles 3 1/2 * 3	
1126	1	OWE Blend Cement 4 1/2 wiper plug	
1110	12 SK	Gilsonite	
1107	1 SK	Flo-Seal	
1118	2 SK	Premium Gel	
1215A	1 gal	KCL	
1111B	2 SK	Sodium Silicate Calchloride	
1123	7000 gal	City Water	
903142	3 hr	Transport Truck	
932152	3 hr	Transport Trailer	
931500	3 hr	80 Vac	

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 11 2007

CONSERVATION DIVISION
WICHITA, KS