

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE**

Form ACO-1
September 1999
Form Must Be Typed

Operator: License # 33365
Name: Layne Energy Operating, LLC
Address: 1900 Shawnee Mission Parkway
City/State/Zip: Mission Woods, KS 66205
Purchaser: _____
Operator Contact Person: M. Brent Natrass
Phone: (913) 748-3960
Contractor: Name: McPherson Drilling
License: 5675

Wellsite Geologist: _____
Designate Type of Completion:
____ New Well ____ Re-Entry Workover
____ Oil ____ SWD ____ SIOW ____ Temp. Abd.
 Gas ____ ENHR ____ SIGW
____ Dry ____ Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: 5/15/06 Original Total Depth: 1185'
____ Deepening Re-perf. ____ Conv. to Enhr./SWD
 Plug Back CIBP 1070' Plug Back Total Depth
 Commingled Docket No. _____
____ Dual Completion Docket No. _____
____ Other (SWD or Enhr.?) Docket No. _____
2/14/2007 _____ 2/20/2007
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 125-31048-00-01 Corrected
County: Montgomery
____ SW ____ NW Sec. 28 Twp. 32 S. R. 16 East West
1980 feet from S / (circle one) Line of Section
661 feet from E / (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
____ (circle one) NE SE NW SW
Lease Name: Tucker Well #: 5-28
Field Name: Cherokee Basin Coal Area
Producing Formation: Cherokee Coals
Elevation: Ground: 797' Kelly Bushing: _____
Total Depth: 1185' Plug Back Total Depth: 1182'
Amount of Surface Pipe Set and Cemented at 40 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from 1182
feet depth to Surface w/ 125 sx cmt.
Co-Dr - 7/22/09

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content N/A ppm Fluid volume _____ bbls
Dewatering method used N/A - Air Drilled
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: *M.B. Natrass*
Title: Agent Date: 6/12/07
Subscribed and sworn to before me this 12th day of June,
20 07.
Notary Public: *M. Allen*
Date Commission Expires: 10/14/2008



KCC Office Use ONLY

Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

RECEIVED
JUN 30 2009

KCC WICHITA

Operator Name: Layne Energy Operating, LLC Lease Name: Tucker Well #: 5-28
 Sec. 28 Twp. 32 S. R. 16 East West County: Montgomery

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: Compensated Density Neutron Dual Induction	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:60%;">Name</td> <td style="width:20%;">Top</td> <td style="width:20%;">Datum</td> </tr> <tr> <td>Pawnee Lime</td> <td>521 GL</td> <td>276</td> </tr> <tr> <td>Excello Shale</td> <td>675 GL</td> <td>122</td> </tr> <tr> <td>V Shale</td> <td>722 GL</td> <td>75</td> </tr> <tr> <td>Mineral Coal</td> <td>762 GL</td> <td>35</td> </tr> <tr> <td>Mississippian</td> <td>1106 GL</td> <td>-309</td> </tr> </table>	Name	Top	Datum	Pawnee Lime	521 GL	276	Excello Shale	675 GL	122	V Shale	722 GL	75	Mineral Coal	762 GL	35	Mississippian	1106 GL	-309
Name	Top	Datum																	
Pawnee Lime	521 GL	276																	
Excello Shale	675 GL	122																	
V Shale	722 GL	75																	
Mineral Coal	762 GL	35																	
Mississippian	1106 GL	-309																	

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacjs Used	Type and Percent Additives
Surface	11"	8.625"	24	40'	Class A	65	Type 1 cement
Casing	6.75"	4.5"	10.5	1182'	Thick Set	125	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
	See Attached		
	2/14/2007 CIBP 1070'		

TUBING RECORD	Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
	2-3/8"	813'		

Date of First, Resumerd Production, SWD or Enhr. 2/20/2007	Producing Method <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)
---	--

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	0	4	20		

Disposition of Gas . **METHOD OF COMPLETION** Production Interval

Vented Sold Used on Lease Open Hole Perf. Dually Comp. Commingled
(If vented, Submit ACO-18.) Other (Specify) _____

RECEIVED
 JUN 30 2009
 KCC WICHITA

Operator Name: Layne Energy Operating, LLC.			
Lease Name: Tucker 5-28			
Sec. 28 Twp. 32S Rng. 16E, Montgomery County			
API: 15-125-31048-00-01			
Shots per Foot	Perforation Record	Acid, Fracture, Shot, Cement Squeeze Record	Depth
4	1091-1094	Riverton-1300# 20/40 sand, 212 bbls wtr, 500 gal 15% HCl acid	1091 - 1094
New Perforations			
4	761 - 763; 723.5 - 726	Mineral; Croweburg -- 5100 # 20/40 Sand + 614 bbls Water + 700 gals 15% HCL	723.5 - 763
4	698 - 700; 674.5 - 680; 646 - 649.5	Iron Post; Mulky Coal; Summit -- 10,500 # 20/40 Sand + 1055 bbls Water + 850 gals 15% HCL	646 - 700

RECEIVED

JUN 30 2009

KCC WICHITA