

ORIGINAL

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form ACO-1  
September 1999  
Form Must Be Typed

WELL COMPLETION FORM  
WELL HISTORY - DESCRIPTION OF WELL & LEASE

*KCC  
M  
9/10/08*

Operator: License # 3728  
Name: Roger Kent dba R.J. Enterprises  
Address: 22082 NE Neosho Road  
City/State/Zip: Garnett, KS 66032  
Purchaser: Plains Marketing, L.P.  
Operator Contact Person: Roger Kent  
Phone: (785) 448-6995 or 448-7725  
Contractor: Name: Roger Kent dba R.J. Enterprises  
License: 3728  
Wellsite Geologist: n/a

Designate Type of Completion:  
 New Well     Re-Entry     Workover  
 Oil     SWD     SIOW     Temp. Abd.  
 Gas     ENHR     SIGW  
 Dry     Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:  
Operator: \_\_\_\_\_

Well Name: \_\_\_\_\_  
Original Comp. Date: \_\_\_\_\_ Original Total Depth: \_\_\_\_\_  
 Deepening     Re-perf.     Conv. to Enhr./SWD  
 Plug Back     Plug Back Total Depth  
 Commingled    Docket No. \_\_\_\_\_  
 Dual Completion    Docket No. \_\_\_\_\_  
 Other (SWD or Enhr.?)    Docket No. \_\_\_\_\_

May 29, 2008	May 31, 2008	May 31, 2008
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 003-24531-00-00  
County: Anderson  
NW    SE    Sec. 7 Twp. 21 S. R. 20  East  West  
1,280 feet from S / N (circle one) Line of Section  
1,020 feet from E / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE SE NW SW  
Lease Name: Charles Melcher Well #: 4-A  
Field Name: Bush City Shoestring  
Producing Formation: Squirrel  
Elevation: Ground: 1,097 ft. Kelly Bushing: \_\_\_\_\_  
Total Depth: 848 ft. Plug Back Total Depth: \_\_\_\_\_  
Amount of Surface Pipe Set and Cemented at 20.7 Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set \_\_\_\_\_ Feet  
If Alternate II completion, cement circulated from 0  
feet depth to 848 ft. w/ 90 sx cm.


Drilling Fluid Management Plan AH II NCR  
(Data must be collected from the Reserve Pit) 10-13-08  
Chloride content none ppm Fluid volume 140 bbls  
Dewatering method used Drilled with fresh water - air dry  
Location of fluid disposal if hauled offsite: \_\_\_\_\_  
Operator Name: \_\_\_\_\_  
Lease Name: \_\_\_\_\_ License No.: \_\_\_\_\_  
Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  East  West  
County: \_\_\_\_\_ Docket No.: \_\_\_\_\_

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: R. Kent  
Title: Agent for R.J. Enterprises Date: September 9, 2008  
Subscribed and sworn to before me this 9th day of September,  
2008.

Notary Public: Donna Manda  
Date Commission Expires: March 16, 2011



**KCC Office Use ONLY**

Letter of Confidentiality Received  
If Denied, Yes  Date: \_\_\_\_\_  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

RECEIVED  
KANSAS CORPORATION COMMISSION  
SEP 09 2008



**R.J. Enterprises**  
**Charles Melcher 4-A**

2	soil	2	start 5-29-08
8	clay & rock	10	finish 5-31-08
30	lime	40	
41	shale	81	
9	lime	90	
112	shale	202	
35	lime	237	
61	shale	298	
108	lime	407	
172	shale	579	
23	lime	602	
61	shale	663	
12	lime	675	
11	shale	686	
9	lime	695	
18	shale	711	
7	lime	718	
23	shale	741	set 20' 7"
4	lime	745	ran 840.3' of 2 7/8
11	shale	756	cement to surface
5	lime	761	with 90 sxs.
9	shale	770	
10	sandy shale	781	odor
7	sandy shale	788	show
2	bk sand	790	show
5	dk shale	795	
22	bk sand	817	good show
9	dk sand	826	good show
22	shale	848	T.D.

RECEIVED  
 KANSAS CORPORATION COMMISSION

SEP 09 2008

CONSERVATION DIVISION  
 WICHITA, KS

**Garnett Siding & Lumber Co.**  
 410 N Maple  
 Garnett, KS 66032  
 (785) 448-7106 FAX (785) 448-7135

Merchant Copy  
**INVOICE**  
 THIS COPY MUST REMAIN AT  
 MERCHANT AT ALL TIMES!


Page: 1	Invoice: <b>10131237</b>
Special Instructions:	Time: 10:51:20 Ship Date: 05/29/08 Invoice Date: 05/29/08 Due Date: 06/09/08
Sale rep #: WAYNE WAYNE STANLEY	Acct. rep. code:
Sold To: <b>ROGER KENT</b> 22082 NE NEOSHO RD GARNETT, KS 66032	Ship To: <b>ROGER KENT</b> (785) 448-6995 <b>NOT FOR HOUSE USE</b> (785) 448-6995
Customer #: 0000357	Customer PO: Order By:

ORDER	SHIP	L	U/M	ITEM#	DESCRIPTION	Alt Price/Uom	PRICE	EXTENSION
60.00	60.00	P	BAG	CPFA	FLY ASH MIX 80 LBS PER BAG	5.4500 BAG	5.4500	327.00
60.00	60.00	P	BAG	CPPC	PORTLAND CEMENT-94#	8.6900 BAG	8.6900	521.40

FILLED BY	CHECKED BY	DATE SHIPPED	DRIVER	Sales total	\$948.40
SHIP VIA Customer Pick up				Taxable	848.40
RECEIVED COMPLETE AND IN GOOD CONDITION				Non-taxable	0.00
X <i>[Signature]</i>				Sales tax	61.94

**TOTAL \$910.34**

1 - Merchant Copy



RECEIVED  
 KANSAS CORPORATION COMMISSION

SEP 09 2008

CONSERVATION DIVISION  
 WICHITA, KS