

**ORIGINAL**

TIGHT

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL COMPLETION FORM**  
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Form ACO-1  
September 1999  
Form Must Be Typed

Operator: License # 32309  
Name: Presco Western, LLC  
Address: 5480 Valmont, Ste. 350  
City/State/Zip: Boulder, CO 80301  
Purchaser: Plains Marketing LP - oil OneOK - gas  
Operator Contact Person: Leonard Witkowski  
Phone: ( 303 ) 444-8881  
Contractor: Name: Cheyenne Drilling LP  
License: 33375  
Wellsite Geologist: None - Boulder office  
Designate Type of Completion:  
 New Well  Re-Entry  Workover  
 Oil  SWD  SIOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc)  
If Workover/Re-entry: Old Well Info as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Original Comp. Date: \_\_\_\_\_ Original Total Depth: \_\_\_\_\_  
 Deepening  Re-perf.  Conv. to Enhr./SWD  
 Plug Back \_\_\_\_\_ Plug Back Total Depth \_\_\_\_\_  
 Commingled \_\_\_\_\_ Docket No. \_\_\_\_\_  
 Dual Completion \_\_\_\_\_ Docket No. \_\_\_\_\_  
 Other (SWD or Enhr.?) \_\_\_\_\_ Docket No. \_\_\_\_\_  
11/15/2005      11/23/2005      1/12/2006  
Spud Date or      Date Reached TD      Completion Date or  
Recompletion Date           Recompletion Date

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 30 2006  
CONSERVATION DIVISION  
WICHITA, KS


API No. 15 - 081-21628-00-00  
County: Haskell  
C    SW    SE    Sec. 7 Twp. 30 S. R. 33  East  West  
660 feet from S N (circle one) Line of Section  
1980' feet from E W (circle one) Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE SE NW SW  
Lease Name: Balck Trusts Well #: 17-07-30-33  
Field Name: Victory  
Producing Formation: St. Louis  
Elevation: Ground: 2959.9 Kelly Bushing: 2970.9  
Total Depth: 5635 Plug Back Total Depth: \_\_\_\_\_  
Amount of Surface Pipe Set and Cemented at 1716 Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set \_\_\_\_\_ Feet  
If Alternate II completion, cement circulated from \_\_\_\_\_  
feet depth to \_\_\_\_\_ w/ \_\_\_\_\_ sx cmt.

**Drilling Fluid Management Plan** Air I MR  
(Data must be collected from the Reserve Pit) 10-24-08  
Chloride content 2700 ppm Fluid volume 1400 bbls  
Dewatering method used Air Evaporation  
Location of fluid disposal if hauled offsite: \_\_\_\_\_  
Operator Name: \_\_\_\_\_  
Lease Name: \_\_\_\_\_ License No.: \_\_\_\_\_  
Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  East  West  
County: \_\_\_\_\_ Docket No.: \_\_\_\_\_

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]  
Title: Regulatory Specialist Date: 3/29/06  
Subscribed and sworn to before me this 29<sup>th</sup> day of March, 2006.  
Notary Public: [Signature]  
Date Commission Expires: 1/26/2008



**KCC Office Use ONLY**  
 Letter of Confidentiality Received  
If Denied, Yes  Date: 03/30/06  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

TIGHT

Side Two

Operator Name: Presco Western, LLC Lease Name: Balck Trusts Well #: 17-07-30-33
Sec. 7 Twp. 30 S. R. 33 [ ] East [x] West County: Haskell

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken [ ] Yes [x] No
Samples Sent to Geological Survey [ ] Yes [x] No
Cores Taken [ ] Yes [x] No
Electric Log Run [x] Yes [ ] No
List All E. Logs Run:
Sonic cement bond, Temperature, Microresistivity, Dual compensated, Dual induction

CASING RECORD [x] New [ ] Used
Report all strings set-conductor, surface, intermediate, production, etc.
Table with columns: Purpose of String, Size Hole Drilled, Size Casing Set (In O.D.), Weight Lbs./ Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives

ADDITIONAL CEMENTING / SQUEEZE RECORD
Table with columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives

PERFORATION RECORD - Bridge Plugs Set/Type
Specify Footage of Each Interval Perforated
Table with columns: Shots Per Foot, PERFORATION RECORD, Acid, Fracture, Shot, Cement Squeeze Record, Depth

TUBING RECORD
Size 2.875 Set At 5631 Packer At Liner Run [ ] Yes [x] No
Date of First, Resumered Production, SWD or Enhr. 1/12/2006
Producing Method [x] Flowing [ ] Pumping [ ] Gas Lift [ ] Other (Explain)
Estimated Production Per 24 Hours: Oil 6 Bbls, Gas 57 Mcf, Water 1 Bbls, Gas-Oil Ratio 9500, Gravity 37.5

Disposition of Gas METHOD OF COMPLETION Production Interval
[ ] Vented [x] Sold [ ] Used on Lease [ ] Open Hole [x] Perf. [ ] Dually Comp. [x] Commingled 5359-5365
(If vented, Submit ACO-18.) [ ] Other (Specify)

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 30 2006
CONSERVATION DIVISION
WICHITA, KS

# ALLIED CEMENTING CO., INC.

21759

EMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
OAKLEY

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 30 2006

CONSERVATION DIVISION  
MICHIGITA, KS

DATE <u>11-24-05</u>	SEC. <u>7</u>	TWP. <u>30S</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>9:00 PM</u>	JOB START <u>10:00 AM</u>	JOB FINISH <u>11:00 AM</u>
LEASE <u>BLACK TRUST</u>	WELL # <u>17</u>	LOCATION <u>SATANTA 1E-1/4N-1/2W</u>			COUNTY <u>MASKELL</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)							

CONTRACTOR CHEYENNE DRILL RIG #1 OWNER SAME

TYPE OF JOB PRODUCTION STRING

HOLE SIZE 7 7/8" T.D. 5635'

CASING SIZE 5 1/2" DEPTH 5632'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 2155'

CEMENT LEFT IN CSG. 21.55'

PERFS.

DISPLACEMENT 13 3/4 AAL

**EQUIPMENT**

PUMP TRUCK CEMENTER TERRY

# 191 HELPER JARROD MAX

BULK TRUCK

# 394 DRIVER LONNIE

BULK TRUCK

# DRIVER

CEMENT

AMOUNT ORDERED 325 SKS ASC 10% SALT

5" GILSONITE 1/2 OF 1% FI-160 1/4" # FLO SEAL

500 GAL WFR-2 2766L

COMMON	@		
POZMIX	@		
GEL <u>6SKs</u>	@	<u>14</u>	<u>84</u>
CHLORIDE	@		
ASC <u>325 SKs</u>	@	<u>11.60</u>	<u>3786.25</u>
SALT <u>30 SKs</u>	@	<u>15.25</u>	<u>472.50</u>
<u>GILSONITE 1625#</u>	@	<u>1.60</u>	<u>975.00</u>
<u>FI-160 153#</u>	@	<u>8.20</u>	<u>1331.20</u>
<u>FLO-SEAL 81#</u>	@	<u>1.28</u>	<u>137.28</u>
<u>WFR-2 500 GAL</u>	@	<u>1.00</u>	<u>500.00</u>
	@		
HANDLING <u>430 SKs</u>	@	<u>1.60</u>	<u>688.00</u>
MILEAGE <u>64 PER SK / MILE</u>	@		<u>774.00</u>
TOTAL			<u>8748.23</u>

**REMARKS:**

MIX 500 GAL WFR-2 MIX 15 SKS  
CEMENT RAT HOLE MIX 10 SKS CEMENT  
MOUSE HOLE MIX 300 SKS ASC 10% SALT  
5" GILSONITE 2766L 1/2 OF 1% FI-160 1/4" # FLO  
SEAL, WASH TRUCK + LINE DISPLACE 13 3/4  
BBL WATER, PLUG LAUNCHED AT 2300 PST.  
FLOAT HOLE

THANK YOU

CHARGE TO: PRESCO-WESTERN

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**SERVICE**

DEPTH OF JOB <u>5632'</u>		
PUMP TRUCK CHARGE		<u>1510.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>30 MILE</u>	@	<u>5.00</u> <u>150.00</u>
MANIFOLD	@	
	@	
	@	
TOTAL		<u>1660.00</u>

**5 1/2" PLUG & FLOAT EQUIPMENT**

<u>1- GUIDE SHOES</u>		<u>160.00</u>
<u>1- AFU INSERT</u>	@	<u>235.00</u>
<u>7- CENTRALIZERS</u>	@	<u>50.00</u> <u>350.00</u>
<u>1- BRACKET</u>	@	<u>140.00</u>
<u>1- PORT COLLAR</u>	@	<u>1750.00</u>
<u>1- RUBBER PLUG</u>	@	<u>10.00</u>
TOTAL		<u>2695.00</u>

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

PRINTED NAME \_\_\_\_\_

# ALLIED CEMENTING CO., INC.

21714

SHIP TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

OAKLAKES

DATE <u>11-17-05</u>	SEC <u>7</u>	TWP. <u>30S</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>1:30 pm</u>	JOB START <u>2:00 pm</u>	JOB FINISH <u>2:45 pm</u>
LEASE <u>Black Trust</u>	WELL # <u>17-07</u>	LOCATION <u>Sadanta 1E 118N</u>	COUNTY <u>Hasell</u>	STATE <u>KS</u>			
OLD OR <u>NEW</u> (Circle one)			<u>112W</u>				

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 30 2006

CONTRACTOR Choyenne Dicks #1

TYPE OF JOB Top off 8 1/2"

HOLE SIZE 12 1/2" T.D.

CASING SIZE 8 1/2" DEPTH 480'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG. 20'

PERFS.

DISPLACEMENT 29.2 BALS

OWNER same

CEMENT

AMOUNT ORDERED 350 10m

370 cc 114# Flo-seal

CONSERVATION DIVISION  
WICHITA, KS

COMMON	<u>350</u>	@ <u>10.00</u>	<u>3500.00</u>
POZMIX		@	
GEL		@	
CHLORIDE	<u>12</u>	@ <u>38.00</u>	<u>456.00</u>
ASC		@	
<u>Flo-seal</u>	<u>87#</u>	@ <u>1.70</u>	<u>147.90</u>
		@	
		@	
		@	
		@	
HANDLING	<u>366</u>	@ <u>1.60</u>	<u>585.60</u>
MILEAGE	<u>.06</u>	<u>15K/mile</u>	<u>658.80</u>
TOTAL			<u>5348.30</u>

EQUIPMENT

PUMP TRUCK CEMENTER Fuzzy

# 273-291 HELPER Andrew

BULK TRUCK

# 353 DRIVER Junior

BULK TRUCK

# DRIVER

REMARKS:

Perf 8 1/2" @ 480'

mix 350 cks

displace plus 40 within

20' of perfs

cement did circulate

plus down @ 2:45 pm

Thanks Fuzzy

+ crew

CHARGE TO: Picco-Western

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

SERVICE

DEPTH OF JOB	<u>480'</u>		
PUMP TRUCK CHARGE			<u>670.00</u>
EXTRA FOOTAGE	<u>180</u>	@ <u>1.55</u>	<u>99.00</u>
MILEAGE	<u>30</u>	@ <u>5.00</u>	<u>150.00</u>
MANIFOLD		@	
		@	
		@	
TOTAL			<u>919.00</u>

PLUG & FLOAT EQUIPMENT

<u>1-8 1/2" Rubber Plug</u>			<u>100.00</u>
		@	
		@	
		@	
		@	
TOTAL			<u>100.00</u>

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE Rodney Gonzales

Rodney Gonzales  
PRINTED NAME

# ALLIED CEMENTING CO., INC. 21795

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Oakley

DATE <u>12-6-05</u>	SEC. <u>7</u>	TWP. <u>30s</u>	RANGE <u>33w</u>	CALLED OUT	ON LOCATION <u>3:00 PM</u>	JOB START <u>3:40 PM</u>	JOB FINISH <u>5:00 PM</u>
LEASE <u>Block Trust</u>		WELL # <u>17-07-30-33</u>	LOCATION <u>Santana 1 E. 1/2 W 1/4</u>			COUNTY <u>Haskell</u>	STATE <u>KS</u>
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR Electrolge well service  
TYPE OF JOB Part collar

OWNER Same

**RECEIVED**  
KANSAS CORPORATION COMMISSION

**MAR 30 2006**

HOLE SIZE	T.D.
CASING SIZE <u>5 1/2</u>	DEPTH
TUBING SIZE <u>2 7/8</u>	DEPTH <u>3076</u>
DRILL PIPE	DEPTH
TOOL <u>Part collar</u>	DEPTH <u>3076</u>
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

CEMENT  
AMOUNT ORDERED 4.50 sks Lite. 4# Flo Seal 1  
Used 7.5 sks

CONSERVATION DIVISION  
WICINITA, KS

**EQUIPMENT**

PUMP TRUCK	CEMENTER <u>Dean</u>
# <u>373-251</u>	HELPER <u>Tarrad Max</u>
BULK TRUCK	
# <u>394</u>	DRIVER <u>Lennie</u>
BULK TRUCK	
#	DRIVER

COMMON	@	
POZMIX	@	
GEL	@	
CHLORIDE	@	
ASC	@	
<u>Liteweight 7.5 sks</u>	@ <u>8.80</u>	<u>660.00</u>
<u>Flo Seal 19#</u>	@ <u>1.70</u>	<u>30.30</u>
	@	
	@	
	@	
	@	
HANDLING <u>48% sks</u>	@ <u>1.60</u>	<u>76.80</u>
MILEAGE <u>64 sk/mile</u>		<u>873.00</u>

TOTAL ~~935.00~~  
2341.30

**REMARKS:**

Pressure Test to 1500#. open  
Tool & pump Int Rate 2 RPM at 1200#  
No Blow. Mix 7.5 sks and shut off

**SERVICE**

DEPTH OF JOB	<u>3076'</u>	
PUMP TRUCK CHARGE		<u>7867.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>30 miles</u>	@ <u>5.00</u>	<u>150.00</u>
MANIFOLD	@	
	@	
	@	

TOTAL 935.00

CHARGE TO: Presco Western  
STREET \_\_\_\_\_  
CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**PLUG & FLOAT EQUIPMENT**

	@	
	@	
	@	
	@	
	@	

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_  
TOTAL CHARGE ~~935.00~~

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE Rodney Gonzales

Rodney Gonzales  
PRINTED NAME

# ALLIED CEMENTING CO., INC. 21672

SHIP TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
OAKLEY

DATE <u>11-16-05</u>	SEC. <u>7</u>	TWP. <u>30S</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION	JOB START <u>7:30 AM</u>	JOB FINISH <u>8:45 PM</u>
LEASE <u>BLACK TRUST</u>		WELL # <u>17-07</u>		LOCATION <u>SATANTA 1E-18N-12W</u>		COUNTY <u>HASKELL</u>	STATE <u>KS</u>
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR CHEYENNE DRILLING #1

TYPE OF JOB SURFACE

HOLE SIZE 12 1/4" T.D. 1715'

CASING SIZE 8 5/8" DEPTH 1716'

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX 1000 MINIMUM 150'

MEAS. LINE \_\_\_\_\_ SHOE JOINT 44'

CEMENT LEFT IN CSG. 44'

PERFS. \_\_\_\_\_

DISPLACEMENT 106 1/2 BBL.

OWNER SAME

CEMENT

AMOUNT ORDERED 150 SKS COM 3% CC

575 SKS LITE 3% CC 1/2" FLO-SEAL

COMMON	<u>150 SKS</u>	@	<u>10.00</u>	<u>1500.00</u>
POZMIX		@		
GEL		@		
CHLORIDE	<u>27 SKS</u>	@	<u>38.00</u>	<u>912.00</u>
ASC		@		
<u>LITE</u>	<u>575 SKS</u>	@	<u>9.30</u>	<u>5347.50</u>
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>778 SKS</u>	@	<u>1.60</u>	<u>1244.80</u>
MILEAGE	<u>60 PER SKI</u>	MILE		<u>1400.00</u>
TOTAL				<u>10894.30</u>

EQUIPMENT

PUMP TRUCK CEMENTER TERRY MAX

# 191 HELPER WAYNE

BULK TRUCK

# 396 DRIVER MIKE

BULK TRUCK

# 299 DRIVER STEVE

REMARKS:

MIX 575 SKS LITE 1/2" FLO

SEAL 150 SKS COM 3% CC

DISPLACE 106 1/2 BBL WATER.

Last Returns Cement Did not

Circulate

THANK YOU

CHARGE TO: PRESCO - WESTERN

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

SERVICE

DEPTH OF JOB 1716'

PUMP TRUCK CHARGE 1320.00

EXTRA FOOTAGE @ \_\_\_\_\_

MILEAGE 30 mi @ 5.00 150.00

MANIFOLD @ \_\_\_\_\_

TOTAL 1470.00

8 5/8" PLUG & FLOAT EQUIPMENT

1- GUIDE SHOE 235.00

1- APU INSERT @ 325.00

4- CENTRALIZERS @ 55.00 220.00

1- BASKET @ 180.00

1- RUBBER PLUG @ 100.00

TOTAL 1060.00

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE Rodney Gonzales Rodney Gonzales  
PRINTED NAME

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 MAR 3 0 2006  
 CONSERVATION DIVISION  
 WICHITA, KS

# ALLIEC CEMENTING CO., INC. 21759

EMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: OAKLEY

CONSERVATION DIVISION  
WICHITA KS

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 3 0 2006

DATE <u>11-24-05</u>	SEC <u>7</u>	TWP. <u>30S</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>9:00 AM</u>	JOB START <u>10:00 AM</u>	JOB FINISH <u>11:00 AM</u>
LEASE <u>BLACK TRUST</u>		WELL # <u>17</u>	LOCATION <u>SATANTA 1E 1/4 N 1/2 W</u>				
COUNTY <u>HASKELL</u> STATE <u>KS</u>							
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR CHEYENNE DRILL RIG #1 OWNER SAME

TYPE OF JOB PRODUCTION STRING

HOLE SIZE 7 7/8" T.D. 5635'

CASING SIZE 5 1/2" DEPTH 5632'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 21.55'

CEMENT LEFT IN CSG. 21.55'

PERFS.

DISPLACEMENT 133 1/2 ABL

CEMENT

AMOUNT ORDERED 325 SKS ASC 109 SALT

5" GILSONITE 1/2 OF 1% FI-160 1/4" FLO SEAL

500 GAL WFR-2 286 GAL

COMMON	@		
POZMIX	@		
GEL	@	<u>6 SKS</u>	<u>74.00</u>
CHLORIDE	@		
ASC	@	<u>325 SKS</u>	<u>3786.25</u>
SALT	@	<u>30 SKS</u>	<u>472.50</u>
	@		
GILSONITE	@	<u>1625 #</u>	<u>975.00</u>
	@		
FI-160	@	<u>153 #</u>	<u>1331.00</u>
FLO-SEAL	@	<u>81 #</u>	<u>137.25</u>
WFR-2	@	<u>500 GAL</u>	<u>500.00</u>
	@		
HANDLING	@	<u>430 SKS</u>	<u>688.00</u>
MILEAGE	@	<u>64 PER SK / MILE</u>	<u>774.00</u>
		TOTAL	<u>8748.75</u>

EQUIPMENT

PUMP TRUCK CEMENTER TERRY

# 191 HELPER JARROD MAX

BULK TRUCK

# 394 DRIVER LONNIE

BULK TRUCK

# DRIVER

**REMARKS:**

MIX 500 GAL WFR-2 MIX 15 SKS CEMENT RAT HOLE MIX 10 SKS CEMENT MOUSE HOLE MIX 300 SKS ASC 109 SALT 5" GILSONITE 286 GAL 1/2 OF 1% FI-160 1/4" FLO SEAL WASH TRUCK + LINE DISPLACE 133 1/2 ABL WATER Plug Landed AT 2300 PSI. FLOAT 16.4

THANK YOU

CHARGE TO: PRESCO-WESTERN

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**SERVICE**

DEPTH OF JOB	<u>5632'</u>	
PUMP TRUCK CHARGE		<u>1510.00</u>
EXTRA FOOTAGE	@	
MILEAGE	<u>30 MILE</u>	@ <u>5.00</u> <u>150.00</u>
MANIFOLD	@	
	@	
	@	
		TOTAL <u>1660.00</u>

**5 1/2" PLUG & FLOAT EQUIPMENT**

1- GUIDE SHOE		<u>160.00</u>
1- AFU INSERT	@	<u>235.00</u>
7- CENTRALIZERS	@ <u>50.00</u>	<u>350.00</u>
2- BASKETS	@	<u>140.00</u>
1- PORT COLLAR	@	<u>175.00</u>
1- RUBBER PLUG	@	<u>60.00</u>
		TOTAL <u>2695.00</u>

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE 

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

PRINTED NAME \_\_\_\_\_