

WELL COMPLETION FORM WELL HISTORY - DESCRIPTION OF WELL & LEASE

OPERATOR: License # 4058 Name: American Warrior, Inc. Address 1: PO Box 399 Address 2: City: Garden City State: KS Zip: 67846 + 0399 Contact Person: Scott Corsair Phone: (785) 398-2270 CONTRACTOR: License # 33323 Name: Petromark Drilling, LLC Wellsite Geologist: Scott Corsair Purchaser: NCRA Designate Type of Completion: [X] New Well [ ] Re-Entry [ ] Workover [X] Oil [ ] SWD [ ] SIOW [ ] Gas [ ] ENHR [ ] SIGW [ ] CM (Coal Bed Methane) [ ] Temp. Abd. [ ] Dry [ ] Other (Core, WSW, Expl., Cathodic, etc.)

RECEIVED JUL 31 2009 KCC WICHITA

If Workover/Re-entry: Old Well Info as follows: Operator: Well Name: Original Comp. Date: Original Total Depth: Deepening Re-perf. Conv. to Enhr. Conv. to SWD Plug Back: Plug Back Total Depth Commingled Docket No.: Dual Completion Docket No.: Other (SWD or Enhr.?) Docket No.: 09/17/2009 09/25/2009 10/05/2009 Spud Date or Recompletion Date Date Reached TD Completion Date or Recompletion Date

API No. 15 - 135-24589 - 0000 Spot Description: 120' S & 260' W SE NW Sec. 36 Twp. 19 S. R. 22 East West 2100 Feet from North South Line of Section 1720 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Ness Lease Name: Williams Well #: 9 Field Name: Schaben Producing Formation: Mississippian Elevation: Ground: 2249' Kelly Bushing: 2255' Total Depth: 4370' Plug Back Total Depth: 4369' Amount of Surface Pipe Set and Cemented at: 227 Feet Multiple Stage Cementing Collar Used? Yes No If yes, show depth set: 2463 Feet If Alternate II completion, cement circulated from: 2463 feet depth to: surface w/ 300

Drilling Fluid Management Plan (Data must be collected from the Reserve Pit) Chloride content: 42,500 ppm Fluid volume: 400 bbls Dewatering method used: evaporate Location of fluid disposal if hauled offsite: Operator Name: Lease Name: License No.: Quarter Sec. Twp. S. R. East West County: Docket No.:

ALTZ-DG-8/5/09 sx cmt

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Title: Petroleum Engineer Date: 05/07/2009

Subscribed and sworn to before me this 7th day of May 20 09

Notary Public: Denise Corsair Date Commission Expires: 8-15-12

NOTARY PUBLIC - State of Kansas DENISE CORSAIR My Appt. Exp. 8-15-12

KCC Office Use ONLY Letter of Confidentiality Received [X] If Denied, Yes [ ] Date: Wireline Log Received [X] Geologist Report Received [X] UIC Distribution [ ]

Operator Name: American Warrior, Inc. Lease Name: Williams Well #: 9  
 Sec. 36 Twp. 19 S. R. 22  East  West County: Ness

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Attach Additional Sheets)</i>  Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No  Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i>  List All E. Logs Run: <b>Dual Induction, Compensated Neutron/Density</b>	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample  <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:70%;">Name</td> <td style="width:15%;">Top</td> <td style="width:15%;">Datum</td> </tr> <tr> <td>Anhydrite</td> <td>1468</td> <td>+787</td> </tr> <tr> <td>Heebner</td> <td>3718</td> <td>-1463</td> </tr> <tr> <td>Lansing</td> <td>3767</td> <td>-1512</td> </tr> <tr> <td>Pawnee</td> <td>4188</td> <td>-1933</td> </tr> <tr> <td>Ft. Scott</td> <td>4269</td> <td>-2014</td> </tr> <tr> <td>Cherokee</td> <td>4290</td> <td>-2035</td> </tr> <tr> <td>Mississippian</td> <td>4353</td> <td>-2098</td> </tr> </table>	Name	Top	Datum	Anhydrite	1468	+787	Heebner	3718	-1463	Lansing	3767	-1512	Pawnee	4188	-1933	Ft. Scott	4269	-2014	Cherokee	4290	-2035	Mississippian	4353	-2098
Name	Top	Datum																							
Anhydrite	1468	+787																							
Heebner	3718	-1463																							
Lansing	3767	-1512																							
Pawnee	4188	-1933																							
Ft. Scott	4269	-2014																							
Cherokee	4290	-2035																							
Mississippian	4353	-2098																							

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4"	8 5/8"	23	227'	Common	160	2% gel, 3% CC
Production	7 7/8"	5 1/2"	15.5	4369'	Swift EA-2	150	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input checked="" type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone	2463'-Surface	Swift SMD	300	1/4# flocele

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4352-4368.5'		

TUBING RECORD:	Size: <u>2 3/8"</u>	Set At: <u>4343'</u>	Packer At: <u>NA</u>	Liner Run: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumed Production, SWD or Enhr. <u>10/05/2007</u>		Producing Method: <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls. <u>25</u>	Gas Mcf	Water Bbls. <u>10</u>	Gas-Oil Ratio <u>40</u>

DISPOSITION OF GAS: <input type="checkbox"/> Vented <input type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	METHOD OF COMPLETION: <input type="checkbox"/> Open Hole <input checked="" type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <input type="checkbox"/> Other (Specify) _____	PRODUCTION INTERVAL: <u>4352-4368.5' Perf</u>
---	---	--



CHARGE TO: AMERICAN WARRIOR INC.  
 ADDRESS:  
 CITY, STATE, ZIP CODE:

TICKET

No 12833

PAGE 1 OF 1

RECEIVED  
 JUL 31 2009  
 MCC WICHITA

SERVICE LOCATIONS: 1. NESS CITY, KS  
 WELL/PROJECT NO.: 9  
 LEASE: WILLIAMS  
 COUNTY/PARISH: NESS  
 STATE: KS  
 CITY: NESS CITY, KS  
 DATE: 10-1-07  
 OWNER: SAME  
 TICKET TYPE:  SERVICE  
 SALES  
 CONTRACTOR: H-D  
 RIG NAME/NO.:  
 SHIPPED VIA: CT  
 DELIVERED TO: LOCATION  
 ORDER NO.:  
 WELL TYPE: OIL  
 WELL CATEGORY: DEVELOPMENT  
 JOB PURPOSE: COMBAT PORT COLLAR  
 WELL PERMIT NO.:  
 WELL LOCATION: RAZIN, KS - SEC 34W, S5  
 REFERRAL LOCATION:  
 INVOICE INSTRUCTIONS:

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		UNIT PRICE		AMOUNT
		LOC	ACCT	DF		QTY.	U/M	QTY.	U/M	
575		1			MILEAGE " 104	20	MR		4.00	80.00
577		1			PUMP SERVICE	1	JOB		850.00	850.00
105		1			PORT COLLAR OPENING TOOL	1	JOB		400.00	400.00
330		1			SWIFT MULTI-DENSITY STAINLESS	300	CRS		14.50	4350.00
276		1			FLOCCIE	81	URS		1.25	101.25
287		1			CASSTOP	100	URS		7.00	700.00
290		1			D-AD	3	GNL		32.00	96.00
581		1			SERVICE CHARGE COMBAT	325	SHS		1.10	357.50
683		1			DRAZAGE	324.11	URS	324.11	1.00	324.11

**LEGAL TERMS:** Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X *[Signature]*  
 DATE SIGNED: 10-1-07  
 TIME SIGNED: 1600  
 -A.M.  
 -P.M.

REMIT PAYMENT TO:  
 SWIFT SERVICES, INC.  
 P.O. BOX 466  
 NESS CITY, KS 67560  
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	7258.86
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR: *[Signature]*  
 APPROVAL:

Thank You!

JOB LOG.

SWIFT Services, Inc.

DATE 10-1-07 PAGE NO. 1

CUSTOMER AMERICAN WARRIOR LDC WELL NO. 19 LEASE WILLIAMS JOB TYPE COMBAT PORT COLLAR TICKET NO. 12833

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL)(GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1600							ON LOCATION
								2 1/2 x 3/2 PORT COLLAR = 2163'
	1655				✓		1000	PSE TEST CASING - HELD
	1700	2 1/2	2	✓		500		OPN PORT COLLAR - INT RATE
	1705	4	139	✓		450		MAX COMBAT LD - 250 SPS SMD
		3	14			200		TL - 50 SPS SMD W/ GAS TOP
	1750	3	9	✓		350		DISPENSE COMBAT
	1800				✓		1000	CLOSE PORT COLLAR - PSE TEST - HELD
								CIRCULATE 15 SPS COMBAT TO PSE
	1810	3	25		✓		400	RUN 4 JS CIRCULATE CLEAN
								WASH TRUCK
								PULL TOOLS
	1900							JOB COMPLETE

RECEIVED  
JUL 31 2009  
KCC WICHITA

THANK YOU  
WALSH, BERT, SLANE, JEFF



CHARGE TO: AMERICAN WARRIOR INC.  
 ADDRESS:  
 CITY, STATE, ZIP CODE:

TICKET

No 12827

RECEIVED  
 JUL 31 2009  
 KCC WICHITA

PAGE 1 OF 2

SERVICE LOCATIONS: 1. WELLS, COM, KS  
 WELL/PROJECT NO. #9 LEASE WILLIAMS COUNTY/PARISH NESS STATE KS CITY  
 DATE 9-25-07 OWNER SAME  
 2. TICKET TYPE [X] SERVICE [ ] SALES CONTRACTOR Petro-max Drilling RIG NAME/NO. SHIPPED VIA DELIVERED TO HOUTZOW ORDER NO.  
 3. WELL TYPE OIL WELL CATEGORY DEVELOPMENT JOB PURPOSE 5 1/2" LONGSTRAW WELL PERMIT NO. WELL LOCATION BAZZIE VS-6S, 3/4 W, S.W. 1/4  
 4. REFERRAL LOCATION INVOICE INSTRUCTIONS

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE		AMOUNT
		LOC	ACCT	DF								
575		1			MILEAGE # 104	25		MI		4.00		100.00
578		1			PUMP SERVICE	1		JOB	4370	1250.00		1250.00
221		1			LIQUID REC.	2		GAL		26.00		52.00
281		1			MUD FLUSH	500		GAL		.75		375.00
402		1			CENTRALIZERS	10		EA	5 1/2"	95.00		950.00
403		1			CONWT BASKETS	2		EA		290.00		580.00
404		1			PORT COLLAR TOP JO # 417	1		EA	2463	2300.00		2300.00
406		1			LATCH DOWN PLUG - RAFFLE	1		EA		235.00		235.00
407		1			INSERT FLOAT SHOE W/AUTO FOLL	1		EA		310.00		310.00
419		1			ROTATING HEAD RENTAL	1		JOB		250.00		250.00

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.  
 MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS.  
 X [Signature]  
 DATE SIGNED 9-25-07 TIME SIGNED 0030 [ ] A.M. [X] P.M.

REMIT PAYMENT TO:  
 SWIFT SERVICES, INC.  
 P.O. BOX 466  
 NESS CITY, KS 67560  
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	AMOUNT
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				#1	6402.00
WE UNDERSTOOD AND MET YOUR NEEDS?				#2	2916.24
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?					
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TAX	
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND				TOTAL	

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR [Signature]

APPROVAL

Thank You!



JOB LOG.

SWIFT Services, Inc.

DATE 9-25-07 PAGE NO. 1

CUSTOMER AMERICAN WARRIOR EX. WELL NO. H 9 LEASE WILLIAMS JOB TYPE S/B LOGGING TICKET NO. 12827

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	2300							ON LOCATION
	2330							START 5 1/2" CASING
								TD- 4370 SET = 4369
								MD- 4373 5/2" / FT 15.5
								SS- 42.60
								CORRAIDOS - 1, 3, 4, 5, 46, 48, 49, 50, 52, 70
								GMT BKTS - 6, 47
								PORT COLLAR - 2'63 TOP JT # 47
	0130							DROP BALL - CALCULATE ROTATE
	0233	6	12		✓		450	PUMP 500 GAL MUD FLUSH "
	0235	6	20		✓		450	PUMP 20 BRIS KCL FLUSH "
	0240		4					PLUG RH
	0243	5 1/2	36		✓		300	MIX CEMENT 150SIN EA-1 W/ADDITIONS "
	0252							WASH OUT PUMP - LINES
	0254							RELEASE LATCH DOWN PLUG
	0255	7	0		✓			DISPLACE PLUG "
		7	93				700	SHOT OFF ROTATING
	0310	6 1/2	103.1				1500	PLUG DOWN - PSE UP LATCH IN PLUG
	0312						OK	RELEASE PSE - HELL
								WASH NACK
	0400							JOB COMPLETE

RECEIVED  
JUL 31 2009  
KCC WICHITA

THANK YOU  
WAYNE BRINT RYAN

# ALLIED CEMENTING CO., INC.

30414

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Great Bend

DATE <u>9-17-07</u>	SEC. <u>310</u>	TWP. <u>19S</u>	RANGE <u>22W</u>	CALLED OUT <u>8:00pm</u>	ON LOCATION <u>9:30pm</u>	JOB START <u>1:00 AM</u>	JOB FINISH <u>2:00 AM</u>
<u>Pillars</u> LEASE	WELL# <u>1</u>	LOCATION <u>Bazine 75 3/4 W 5 1/2 N 10</u>		COUNTY <u>NESS</u>	STATE <u>KS</u>		

CONTRACTOR Patronmark #2  
 TYPE OF JOB SURFACE  
 HOLE SIZE 12 1/4 T.D. 229  
 CASING SIZE 8 5/8 #24 DEPTH 227  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE 4 1/2 DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX 200 MINIMUM 50  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT 15'  
 CEMENT LEFT IN CSG. 15'  
 PERFS. \_\_\_\_\_

OWNER AMERICAN WARRIOR  
 CEMENT  
 AMOUNT ORDERED 1605X COMMON + 3% CC + 2% GEL

DISPLACEMENT FRESH WATER 13 1/2 BBLs  
 EQUIPMENT

PUMP TRUCK CEMENTER DWAYNE W  
 # 120 HELPER DAVID J  
 BULK TRUCK  
 # 341 DRIVER DEREK D  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

COMMON \_\_\_\_\_ @ \_\_\_\_\_  
 POZMIX \_\_\_\_\_ @ \_\_\_\_\_  
 GEL \_\_\_\_\_ @ \_\_\_\_\_  
 CHLORIDE \_\_\_\_\_ @ \_\_\_\_\_  
 ASC \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 HANDLING \_\_\_\_\_ @ \_\_\_\_\_  
 MILEAGE \_\_\_\_\_ @ \_\_\_\_\_

REMARKS

pipe on bottom GREAT CIRCULATION  
pump 1605X COMMON + 3% CC + 2% GEL  
SHOT DOWN RELEASED PUMP  
and DISP WITH 13 1/2 BBLs FRESH WATER  
SHUT IN CEMENT DIP  
CIRCULATE PUMP THREW SWEDGE  
VALVE  
RIG DOWN

RECEIVED  
 JUL 31 2009  
 SERVICE  
 KCC WICHITA

DEPTH OF JOB 229  
 PUMP TRUCK CHARGE \_\_\_\_\_  
 EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_  
 MILEAGE \_\_\_\_\_ @ \_\_\_\_\_  
 MANIFOLD HEAD RENT @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_

CHARGE TO: AMERICAN WARRIOR  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

TOTAL \_\_\_\_\_

PLUG & FLOAT EQUIPMENT

1 8 3/8 wooden  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE [Signature]

[Signature]  
 PRINTED NAME