


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rooks County, Sec. 35 Twp. 10 Rge. 17W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
N/2 NE NE
Lease Owner Edmiston Oil Co., Inc.
Lease Name Whisman #3 Well No.
Office Address 800 Vickers/KSB&T Bldg., Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4/16/81 19
Plugging completed 4/28/81 19
Reason for abandonment of well or producing formation
Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 3699'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	263'	None
				5 1/2"	3699'	2705'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Pushed plug to 3000' and set 5 sacks cement. Shot pipe at 2684'. Pulled 38 joints of yellow wrap and 43 joints black pipe. Plugged well with 23 sacks gel, 4 sacks hulls, 8-5/8" plug and 140 sacks 50/50 pos 6% gel. Plugging complete.

RECEIVED
STATE CORPORATION COMMISSION
5-5-81
MAY 5 1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of May, 19 81

My commission expires



Joan Kelso
Notary Public.

15-163-20627-0000

DRILLERS' WELL LOG

DATE COMMENCED: August 29, 1976
DATE COMPLETED: September 7, 1976

Edmiston Oil Company
WHISMAN # 3
N/2 NE NE
Sec 35-T10S-R17W
Rooks County, Kansas

ELEVATION: 2072 K.B.

0 - 50' Post Rock
50 - 1165' Shale, Clay, Sand
1165 - 1289' Shale
1289 - 1325' Anhydrite
1325 - 1902' Shale
1902 - 3233' Shale and Lime
3233 - 3237' Shale
3237 - 3256' Shale and Lime
3256 - 3277' Lime and Shale
3277 - 3525' Lime
3525 - 3575' Lime and Shale
3575 - 3671' Lime, Chert, Shale
3671 - 3700' Dolomite
3700' RTD

FORMATION DATA

Anhydrite 1289
Heebner 3233
Toronto 3256
Lansing K.C. 3277
Base K.C. 3525
Conglomerate 3575
Arbuckle 3671
RTD 3700

SURFACE PIPE:

Set used 28#, 8 5/8" pipe @ 263'
w/160 sacks Common, 2% Gel, 3% cc.

PRODUCTION PIPE:

Set new and used 5 1/2" casing at
3699' w/150 sacks 50/50 Pozmix,
2% Gel, salt sat. w/10 bbl
salt flush ahead.

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

RECEIVED
STATE CORPORATION COMMISSION

APR 13 1981

Larry Curtis

Wichita, Kansas

Subscribed and sworn to before me this 9th day of September, 1976.

Dorothy M. Hague

Notary Public

My Commission Expires: April 11, 1978

