

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rooks SEC. 35 TWP. 10S RGE. 17W E/W
Location as in quarters or footage from lines:
SE NW NW

Locate Well
correctly on above
Section Platt.

Lease Owner Lee Phillips Oil Company
Lease Name Whisman Well No. 1
Office Address 125 N. Market, Suite 1532, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole.
Date Well Completed April 19, 1983
Application for plugging filed 5-3-83
Plugging commenced 4-19-83
Plugging completed 4-19-83
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation _____ Depth to top _____ bottom _____ T.D. 3700'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0'	249'	8-5/8"	242.56'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.


Plugged with 20 sacks cement at 3630';
20 sacks cement at 1320'; 100 sacks
cement at 870'; 40 sacks cement at 270';
solid bridge plug and 10 sacks cement at
40'; and 10 sacks cement in rat hole.
(50-50 Pozmix Cement, 6% Gel, 3% CaCl2)

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Cementing Co.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
John D. Knightley, Agent (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
221 S. Broadway, Wichita, KS 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 83

My Commission expires: March 12, 1987

Stella J. Lips Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
5-9-83
MAY 09 1983

RECEIVED
STATE CORPORATION COMMISSION
MAY 09 1983

CONSERVATION DIVISION
Wichita, Kansas

15-163-21998-0000

Lee Phillips Oil Company -
125 N. Market, Suite 1532
Wichita, Kansas 67202

Whisman #1
SE NW NW Sec. 35-10S-17W
Rooks County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: April 13, 1983
Completed: April 19, 1983

Drillers Log

Post Rock	65
Blue Shale	135
Clay	252
Blue Shale & Sand	776
Hard Sandstone	785
Sand & Red Bed	1195
Shale & Red Bed	1316
Anhydrite	1351
Shale & Shells	2445
Shale & Lime	3150
Lime & Shale	3295
Lime	3600
Shale & Lime	3660
Lime	3700 RTD

Casing: 249' 8-5/8" cemented with 200 sacks 50-50 Pozmix Cement,
2% Gel, 3% Calcium Chloride.

RECEIVED
STATE CORPORATION COMMISSION

MAY 09 1983

CONSERVATION DIVISION
Wichita, Kansas