


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pooks County, Sec. 8 Twp. 10S Rge. 18E (E) (W)
Location as "NE/CNW/SW" or footage from lines MT SE ST
Lease Owner Transit Corporation & Davis Brothers
Lease Name Abercrombie Well No. 1
Office Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed February 18, 19 58
Application for plugging filed February 18, 19 58
Application for plugging approved February 18, 19 58
Plugging commenced February 18, 19 58
Plugging completed February 18, 19 58
Reason for abandonment of well or producing formation No Production

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker, 805 W. Main, Victoria, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	182'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 550', set plug, cemented with 20 sacks of cement, filled hole with heavy drilling mud to 170', set plug, cemented with 20 sacks of cement, filled hole with heavy drilling mud to 40', cemented with 10 sacks of cement to bottom of cellar.

3-4-58
MAR 8 1958

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Building, Oklahoma City 1, Oklahoma

STATE OF OKLAHOMA, COUNTY OF OKLAHOMA, ss.
Paul E. Gathers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul E. Gathers

(Address)

SUBSCRIBED AND SWORN to before me this 28th day of February, 19 58

John J. Trook
Notary Public.

My commission expires September 23, 1958

FILED MAR 8 1958
BOOK PAGE 85 LINE 7

DRILLER'S WELL LOG

Transit Corporation-Abercrombie #1 located in NW SE SW of
Section 8-10S-18W, Rooks County, Kansas

Commenced: February 5, 1958
Completed: February 18, 1958
Elevation: 2196 K.B.

Casing 8 5/8" @182'
Cemented 130 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Clay & Shale	0	182
Shale & Shells	182	1090
Sand	1090	1170
Shale & Shells	1170	1617
Anhydrite	1617	1654
Shale & Shells	1654	2115
Shale & Lime Streaks	2115	2225
Lime & Shale Streaks	2225	2370
Lime & Shale	2370	2470
Lime with Shale Streaks	2470	2585
Lime & Shale	2585	2734
Lime with Shale Streaks	2734	2830
Shale	2830	3047
Lime & Shale Streaks	3047	3141
Lime	3141	3241
Lime & Shale Streaks	3241	3303
Lime & Shale	3303	3337
Lime	3337	3489
Lime & Shale	3489	3507
Lime & Shale Streaks	3507	3546
Lime	3546	3600
Lime & Chert	3600	3610
Lime	3610	3685
Conglomerate & Chert	3685	3757
Arbuckle	3757	3795 T.D.

Formation Tops

Topeka	3184'
Heebner	3399'
Toronto	3418'
Lansing	3442'
Base K.C.	3669'
Conglomerate	3684'
Simpson Shale	3733'
Simpson Dolomite	3740'
Arbuckle	3785'
Total Depth	3795'

I hereby Certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.

Subscribed and sworn to before me
this 25th day of February, 1958.

TRANSIT CORPORATION

By Paul E. Gathers

My Commission expires September 23, 1958

Jo Ann Trook
Notary Public

