

LEASE NAME Ganoung A

WELL NUMBER #1

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 13 TWP. 10 SRGE. 18 (N)

COUNTY Rooks

Date Well Completed 2-25-82

Plugging Commenced 12-12-96

Plugging Completed 12-12-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR AFG Energy Inc.

ADDRESS P.O. Box 458 Hays, Ks. 67601-0458

PHONE#(913) 625-6374 OPERATORS LICENSE NO. 03456

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-3-96 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Conglomerate Depth to Top 3666' Bottom 3670' T.O. 3690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Conglomerate	Oil & Water	3666'	3670'	8 5/8"	250	None
				4 1/2"	3760'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set
Hooked to 8 5/8" Mixed 10 sxs 60/40 Poz., 10% gel. Pressured to 500#. Ran tubing to 3665'
open ended. Mixed 350# Hulls & 100 sxs. 60/40 Poz., 10% gel. Pulled tubing to 1588'. Mixed
70 sxs and cement circulated. Pulled tubing out & hooked to 4 1/2" casing. Mixed 15 sxs. of
same. Pressured to 500#. SIP - 300#.

Name of Plugging Contractor Allied License No. 12-17-96

Address Russell, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.

STATE OF Kansas COUNTY OF Ellis, ss.


Terry W. Piesker

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 458 Hays, Ks. 67601-0458



AND SWORN TO before me this 16th day of December, 19 96

Linda K. Pfannenstiel
Notary Public

My Commission Expires: 2/5/2000

USE ONLY ONE SIDE OF EACH FORM