

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NE

SEC. 29 TWP. 12 RGE. 14 W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Foster Odell at 10th Street

Operator Crown Oil Co, Inc Address Great Bend, Kans

Field _____ County Russell

Total Depth 2844 Feet.

(Describe briefly the manner in which the well was plugged)

~~8 5/8" at 693' with 300 sax cement behind. 5 1/2" at 2841'~~
~~with 75 Sax cement behind.~~

~~Filled with chat to 2830', set 4 sax cement with dump bailer
pulled 2494' 5 1/2", filled hole with mud to 250', set rock bridge
and 15 sax cement, filled with mud to 40', set rock bridge
and 10 sax cement to bottom cellar.~~

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 - 1950
CONSERVATION DIVISION
Wichita, Kansas
10-02-50

PLUGGING
FILE SEC 29 T 12 R 14 W
BOOK PAGE 32 LINE 13

[Signature]
District Conservation Agent
Date 9-30-50