

15-167-00307-00-00  
DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 55-4

LOCATION NW NW NE

SEC. 21 TWP. 12 RGE. 15W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. # 1 Lease Clarke

Operator Louis M. Mai Operations Address Box 33, Russell, Kansas

Field \_\_\_\_\_ County Russell

Total Depth 3175 Feet.

Plugging Contractor Barnes and Sons Pipe Pulling Co.

Plugging Contractor's License No. # 9

Address 1450 Maple, Russell, Kansas

(Describe Briefly the manner in which the well was plugged)

Sand back to 3162' and run 5 sax cement with dump bailer. Shot  
pipe off--pulled same. Mud to 250'. Set rock bridge and run 25 sax  
cement. Mud to 40'. Set rock bridge and run 10 sax cement which  
cemented to the base of the cellar.

Donald Truman  
District Conservation Agent

Date November 13, 1957

RECEIVED  
STATE OF KANSAS  
11-19-1957  
NOV 19 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 21 T. 12 R. 15W  
BOOK PAGE 55 LINE 4