

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form ACO-1  
September 1999  
Form Must Be Typed

**WELL COMPLETION FORM**  
**WELL HISTORY - DESCRIPTION OF WELL & LEASE**

ORIGINAL

Operator: License # 32710  
Name: Laymon Oil II, LLC  
Address: 1998 Squirrel Road  
City/State/Zip: Neosho Falls, KS 66758  
Purchaser: Coffeyville Resources  
Operator Contact Person: Kenneth Laymon  
Phone: (620) 963-2495  
Contractor: Name: Kelly Down Drilling Co., Inc  
License: 5661  
Wellsite Geologist: none

Designate Type of Completion:  
 New Well     Re-Entry     Workover  
 Oil     SWD     SLOW     Temp. Abd.  
 Gas     ENHR     SIGW  
 Dry     Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_

Original Comp. Date: \_\_\_\_\_ Original Total Depth: \_\_\_\_\_  
 Deepening     Re-perf.     Conv. to Enhr./SWD  
 Plug Back     Plug Back Total Depth  
 Commingled    Docket No. \_\_\_\_\_  
 Dual Completion    Docket No. \_\_\_\_\_  
 Other (SWD or Enhr.?)    Docket No. \_\_\_\_\_  
11/25/05    11/28/05    <sup>12/10/05</sup> 11/28/05  
Spud Date or    Date Reached TD    Completion Date or  
Recompletion Date    Recompletion Date

API No. 15 - 207-26954-00-00  
County: Woodson  
N2-SE-NE Sec. 04 Twp. 24 S. R. 16  East  West  
3615 feet from (S) / N (circle one) Line of Section  
1320 feet from (E) / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE (SE) NW SW  
Lease Name: Sturdivan #4 Well #: 21-05  
Field Name: Vernon


Producing Formation: Squirrel  
Elevation: Ground: n/a Kelly Bushing: n/a  
Total Depth: 1120 Plug Back Total Depth: 1115  
Amount of Surface Pipe Set and Cemented at 40.20 Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set \_\_\_\_\_ Feet  
If Alternate II completion, cement circulated from 40  
feet depth to surface w/ 10 sx cmt.

Drilling Fluid Management Plan Air II NOR  
(Data must be collected from the Reserve Pit) 9-8-08  
Chloride content \_\_\_\_\_ ppm Fluid volume \_\_\_\_\_ bbls  
Dewatering method used \_\_\_\_\_  
Location of fluid disposal if hauled offsite: \_\_\_\_\_  
Operator Name: \_\_\_\_\_  
Lease Name: \_\_\_\_\_ License No.: \_\_\_\_\_  
Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  East  West  
County: \_\_\_\_\_ Docket No.: \_\_\_\_\_  
**RECEIVED**  
**DEC 16 2005**  
**KCC WICHITA**

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Regina Laymon  
Title: Owner Date: 12/12/05  
Subscribed and sworn to before me this 12 day of December  
2005.

Notary Public: Regina Laymon  
Date Commission Expires: 07-21-09  


**KCC Office Use ONLY**  
NO Letter of Confidentiality Attached  
If Denied, Yes  Date: \_\_\_\_\_  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

Operator Name: Laymon Oil II, LLC Lease Name: Sturdivan #4 Well #: 21-05  
 Sec. 04 Twp. 24 S. R. 16  East  West County: Woodson

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken  Yes  No  
*(Attach Additional Sheets)*

Samples Sent to Geological Survey  Yes  No

Cores Taken  Yes  No

Electric Log Run  Yes  No  
*(Submit Copy)*

List All E. Logs Run:

Log Formation (Top), Depth and Datum  Sample  
 Name Top Datum  
 attached

**RECEIVED**  
**DEC 16 2005**  
**KCC WICHITA**

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	10 1/14"	8 5/8"	24#	40'	common	10	2%
Production	5 7/8"	2 7/8"	6.7	1115'	common	178	50/50 poz
Tubing		1"	1.8#	1050'			

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
___ Perforate				
___ Protect Casing				
___ Plug Back TD				
___ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
2	1057 - 1066	75 gal 15% acid w/150 sks sand	1057 - 66

TUBING RECORD	Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No

Date of First, Resumed Production, SWD or Enhr. 12/10/05	Producing Method <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls. 1	Gas Mcf	Water Bbls.	Gas-Oil Ratio Gravity

Disposition of Gas  Vented  Sold  Used on Lease  Open Hole  Perf.  Dually Comp.  Commingled \_\_\_\_\_  
*(If vented, Sumit ACO-18.)*  Other (Specify) \_\_\_\_\_



**CONSOLIDATED**  
OIL WELL  
SERVICES, INC.  
AN INFINITY COMPANY

**REMIT TO**  
Consolidated Oil Well Services, Inc.  
Dept. 1228  
Denver, CO 80256

**MAIN OFFICE**  
P.O. Box 884  
Chanute, KS 66720  
620/431-9210 • 1-800/467-8676  
FAX 620/431-0012

INVOICE Invoice # 201184

Invoice Date: 11/30/2005 Terms: 0/30,n/30 Page 1

LAYMON OIL & K. LAYMON  
1998 SQUIRREL ROAD  
NEOSHO FALLS KS 66758  
(620)963-2495

STURDIVAN 4 #21-05  
4-24-26  
4991  
11/28/05

Part Number	Description	Qty	Unit Price	Total
1107	FLO-SEAL (25#)	2.00	42.7500	85.50
1118B	PREMIUM GEL / BENTONITE	11.00	6.6300	72.93
1124	50/50 POZ CEMENT MIX	178.00	7.5500	1343.90
4402	2 1/2" RUBBER PLUG	1.00	17.0000	17.00
	Description	Hours	Unit Price	Total
164	CEMENT PUMP	1.00	765.00	765.00
164	EQUIPMENT MILEAGE (ONE WAY)	.00	3.00	.00
164	CASING FOOTAGE	1115.00	.00	.00
195	TON MILEAGE DELIVERY	1.00	425.43	425.43

*pd  
ck # 11699  
12/2/05*

**RECEIVED**  
**DEC 16 2005**  
**KCC WICHITA**

Parts:	1519.33	Freight:	.00	Tax:	95.72	AR	2805.48
Labor:	.00	Misc:	.00	Total:	2805.48		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed \_\_\_\_\_ Date \_\_\_\_\_

<b>BARTLESVILLE, OK</b> P.O. Box 1453 74005 918/338-0808	<b>EUREKA, Ks</b> 820 E. 7th 67045 620/583-7664	<b>OTTAWA, Ks</b> 2631 So. Eisenhower Ave. 66067 785/242-4044	<b>GILLETTE, WY</b> 300 Enterprise Avenue 82716 307/686-4914	<b>THAYER, Ks</b> 8655 Dorn Road 66776 620/839-5269
--	---	---	--	---

THE NEW KLEIN LUMBER COMPANY  
 201 W. MADISON  
 P.O. BOX 805  
 IOLA, KS 66749  
 PHONE: (620) 365-2201

CUSTOMER NO.	JOB NO.	PURCHASE ORDER NO.	REFERENCE	TERMS	CLERK	DATE	TIME
3447				NET 16TH OF MONTH	SE	10/20/05	11:20

LAYMON OIL II  
 1998 SQUIRREL RD  
 NEOSHO FALLS KS 66758

S  
 BUTLER #1-05  
 DELIVER TO SHOP BY 9:00 TUES  
 MORNING  
 O

DOCH 69653  
 \*\*\*\*\*  
 \* INVOICE \*  
 \*\*\*\*\*

TAX : 001 IOLA IOLA

QUANTITY		UM	SKU	DESCRIPTION	UNITS	PRICE/PER	EXTENSION
SHIPPED	ORDERED						
50		EA	PC	PORTLAND CEMENT	50	7.99 /EA	399.50
50		EA	80FA	FLY ASH CON	50	3.85 /EA	192.50

X		RECEIVED BY	** AMOUNT CHARGED TO STORE ACCOUNT **	635.22	TAXABLE	592.00
					NON-TAXABLE	0.00
					SUBTOTAL	592.00
					TAX AMOUNT	43.22
					TOTAL AMOUNT	635.22

RECEIVED  
 DEC 16 2005  
 KCC WICHITA

Kelly Down Drilling Co., Inc  
1998 Squirrel Rd  
Neosho Falls, KS 66758

620-963-2495

fax 620-963-2921

Laymon Oil II, LLC  
1998 Squirrel Road  
Neosho Falls, KS 66758

Sturdivan #4 well # 21-05  
API: 15-207-26954  
Spud Date: 11/25/05  
Comp Date: 11/28/05  
04/24/16 WO CO

Formation	From	To
Soil	0	6
Shale	6	178
Lime & Shale	178	616
Lime	616	656
Big Shale	656	862
Lime & Shale	862	1010
Black Shale	1010	1012
Lime 5'	1012	1015
Mucky Shale	1015	1050
Cap Rock 1st	1050	1051
Shale	1051	1054
Cap Rock 2 <sup>nd</sup>	1054	1055
Sand Lower	1055	1066
Shale	1066	1120
Total Depth		1120

RECEIVED  
DEC 16 2005  
KCC WICHITA

Set 40' 8" surface w/10 sks cement.  
Ran 1115' of 2 7/8" 8 rd.  
Seating nipple @ 1050'.