

WELL COMPLETION FORM  
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 32309

Name: Presco Western, LLC

Address 5665 FLATIRON PARKWAY

City/State/Zip BOULDER CO 80301

Purchaser: High Sierra Crude (oil)/BP (gas)

Operator Contact Person: Randy M. Verret

Phone (303) 305-1163

Contractor: Name: Trinidad Drilling

License: 33754

Wellsite Geologist: Not Applicable

Designate Type of Completion

New Well  Re-Entry  Workover

Oil  SWD  SLOW  Temp. Abd.

Gas  ENHR  SIGW

Dry  Other (Core, WSW, Expl., Cathodic, etc.)

If Workover/Reentry: Old Well Info as follows:

Operator: \_\_\_\_\_

Well Name: \_\_\_\_\_

Original Comp. Date \_\_\_\_\_ Original Total Depth \_\_\_\_\_

Deepening  Re-perf.  Conv. to Enhr./SWD

Plug Back  Plug Back Total Depth \_\_\_\_\_

Commingled Docket No. \_\_\_\_\_

Dual Completion Docket No. \_\_\_\_\_

Other (SWD or Enhr?) Docket No. \_\_\_\_\_

1/18/2008 1/30/2008 3/14/2008

Spud Date or Date Reached TD Completion Date or Recompletion Date

API NO. 15- 187-21115-0000

County Stanton

NE - SW - SW - NW Sec. 26 Twp. 29 S. R. 39  E  W

2,273 Feet from S/N (circle one) Line of Section

335 Feet from E/W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) NE SE NW SW

Lease Name LTW Trust Well # 12-E26-29-39

Field Name Big Bow

Producing Formation St. Louis

Elevation: Ground 3,182' Kelley Bushing 3,194'

Total Depth 5,808' Plug Back Total Depth 5,772'

Amount of Surface Pipe Set and Cemented at 1,719 Feet

Multiple Stage Cementing Collar Used?  Yes 2, No

If yes, show depth set 2,835 Feet

If Alternate II completion, cement circulated from \_\_\_\_\_

feet depth to \_\_\_\_\_ w/ \_\_\_\_\_ sx cmt.

Drilling Fluid Management Plan

(Data must be collected from the Reserve Pit)

Air I NR  
10-20-08

Chloride content 1,700 ppm Fluid volume 3,800 bbls

Dewatering method used Air Evaporation

Location of fluid disposal if hauled offsite:

Operator Name Not Applicable

Lease Name \_\_\_\_\_ License No. \_\_\_\_\_

Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  E  W

County \_\_\_\_\_ Docket No. \_\_\_\_\_

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. MarkeT - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature [Signature]

Title Assistant Date 9/11/2008

Subscribed and sworn to before me this 11th day of September

2008

Notary [Signature]

Date Commission Expires 2-12-2008

My Commission Expires 02/12/2011

KCC Office Use ONLY

Letter of Confidentiality Attached

If Denied, Yes  Date: \_\_\_\_\_

Wireline Log Received

Geologist Report Received

UIC Distribution

Operator Name Presco Western, LLC

Lease Name LTW Trust

Well # 12-E26-29-39

Sec. 26 Twp. 29 S.R. 39  East  West

County Stanton

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets.)  Yes  No

Samples Sent to Geological Survey  Yes  No

Cores Taken  Yes  No

Electric Log Run (Submit Copy.)  Yes  No

List All E.Logs Run:

Array Compensated Resistivity Log, Array Sonic Log, Microlog.

Log Formation (Top), Depth and Datums  Sample

Name	Top	Datum
Marmaton	4,488'	-1,294'
Atoka	4,927'	-1,733'
Morrow	5,176'	-1,982'
Chester	5,549'	-2,355'
St. Louis	5,609'	-2,415'

CASING RECORD  New  Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	23.0	1,719'	Lite/CL C	575/150	3%CC/1/4 Flo Sea
Production	7-1/4"	5-1/2"	15.5	5,808'	ASC	100	2%gel/10%salt

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose <input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone	Depth		Type of Cement	#Sacks Used	Type and Percent Additives
	Top	Bottom			

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	5,672 - 5,687' (St. Louis)	1500G 15%NeFe/40Bbls 4%KC1	

TUBING RECORD Size 2-7/8" Set At 5,735' Packer At \_\_\_\_\_ Liner Run  Yes  No

Date of First, Resumed Production, SWD or Enhr. 4/27/2008 Producing Method  Flowing  Pumping  Gas Lift  Other (Explain)

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	15	-0-	-0-	-0-	37.5

Disposition of Gas:  Vented  Sold  Used on Lease  Open Hole  Perforation  Dually Comp.  Commingled  
 (If vented, submit ACO-18.)  Other (Specify) \_\_\_\_\_

METHOD OF COMPLETION

Production Interval

# ALLIED CEMENTING CO., INC. 31980

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Orleans, KS

DATE	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION	JOB START	JOB FINISH
1-20-08	26	29	39w		12:00am	5:00pm	6:00pm
LEASE	WELL #		LOCATION			COUNTY	STATE
Trust	12E		Big Box Rd + 160			Stanton	KS
OLD OR <u>NEW</u> (Circle one)			5' 1/2 s e side				

CONTRACTOR Trinidad 201 OWNER Same  
TYPE OF JOB Surface

HOLE SIZE <u>12 1/4</u> T.D. <u>1719'</u>	CEMENT
CASING SIZE <u>8 9/16</u> DEPTH <u>1703'</u>	AMOUNT ORDERED <u>575 L. 1/2 39cc</u>
TUBING SIZE DEPTH	<u>1 1/4 Class C</u>
DRILL PIPE DEPTH	<u>150 Class C 39cc</u>
TOOL DEPTH	
PRES. MAX MINIMUM	COMMON <u>Class C 150 @ 17 3/4</u> <u>2602.50</u>
MEAS. LINE SHOE JOINT <u>38 1/2</u>	POZMIX @
CEMENT LEFT IN CSG. <u>38 1/2</u>	GEL @
PERFS.	CHLORIDE <u>24 @ 52 1/2</u> <u>1258.00</u>
DISPLACEMENT <u>107.38</u> <u>106.01</u>	ASC @
EQUIPMENT	<u>Lite 575 @ 13 1/2</u> <u>7676.25</u>
	@
	<u>Class C 144 @ 2 1/2</u> <u>324.00</u>
	@
	@
	@
	HANDLING <u>785 @ 2 1/2</u> <u>1687.25</u>
	MILEAGE <u>109 1/2 mile</u> <u>5793.70</u>
	TOTAL <u>19342.80</u>

PUMP TRUCK CEMENTER Fuzzy  
# 431 HELPER Kelly  
BULK TRUCK DRIVER Alvin  
BULK TRUCK DRIVER Darin

RECEIVED  
KANSAS CORPORATION COMMISSION  
SEP 15 2008  
CONSERVATION DIVISION  
WICHITA, KS

**REMARKS:**

Cement did circulate  
approx 30 BHAS  
Lite press 500# hand press 900#  
Clot held  
Plug down @ 5:30pm  
  
Thanks Fuzzy + crew

**SERVICE**

DEPTH OF JOB		
PUMP TRUCK CHARGE		<u>1812.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>82</u>	@ <u>7.00</u>	<u>574.00</u>
MANIFOLD thread	@	<u>113.00</u>
	@	
	@	

TOTAL 2499.00

CHARGE TO: Presco Western LLC  
STREET \_\_\_\_\_  
CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**PLUG & FLOAT EQUIPMENT**

<u>8 9/16</u> {	1- C. nose G. Shoe	<u>282.00</u>
	1- Successal Clot collar	<u>675.00</u>
	1- Basket	<u>248.00</u>
	10- Cent	<u>620.00</u>
	1- rubber plug	<u>113.00</u>

TOTAL 1938.00

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_  
TOTAL CHARGE \_\_\_\_\_  
DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE [Signature] MARK KNEELAND  
PRINTED NAME

# ALLIED CEMENTING CO., INC.

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: 26785  
Liberal, KS

DATE <u>1-29-08</u>	SEC. <u>26</u>	TWP. <u>29S</u>	RANGE <u>39W</u>	CALLED OUT	ON LOCATION <u>2:00 pm</u>	JOB START <u>8:30 pm</u>	JOB FINISH <u>9:30 pm</u>
LEASE <u>ITW Trust</u>	WELL # <u>12-EA</u>	LOCATION <u>Big Bow - 3S, E into</u>		COUNTY <u>Stanton</u>	STATE <u>KS</u>		
OLD OR <u>(NEW)</u> (Circle one)							

CONTRACTOR Trinidad #201

TYPE OF JOB 5 1/2 Production

HOLE SIZE 7 7/8 T.D. 5808

CASING SIZE 5 1/2 K.S.# 15.5 DEPTH 5812

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL Port Collar DEPTH \_\_\_\_\_

PRES. MAX 1100 MINIMUM 150

MEAS. LINE \_\_\_\_\_ SHOE JOINT 30.57

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT 138 bbls.

EQUIPMENT

PUMP TRUCK CEMENTER Abel, Max, Kirby

# 417 HELPER Don

BULK TRUCK

# 457-239 DRIVER Lalo

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

*Break circ.*

*Mix 100 sks ASC - 25 sks for Port + Mouse hole*

*Drop plug displace CSG*

*Load plug float held*

*Circ. cut*

CHARGE TO: Presco Western

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

OWNER \_\_\_\_\_

CEMENT

AMOUNT ORDERED 100 sks ASC + 2% Gel

10% Salt, 5# Gilsomite, 2% FL-160

COMMON \_\_\_\_\_ @ \_\_\_\_\_

POZMIX \_\_\_\_\_ @ \_\_\_\_\_

GEL 2 sks @ \$18.75 \$37.50

CHLORIDE \_\_\_\_\_ @ \_\_\_\_\_

ASC 100 sks @ \$16.75 \$1675.00

Salt 6 cwt @ \$21.00 \$1296.00

Gilsomite 500# @ 80¢ \$400.00

FL-160 47# @ \$12.00 \$564.00

WERIE 500 gal @ \$1.15 \$575.00

HANDLING 130 sks @ \$2.15 \$279.50

MILEAGE .09/sk/mi \$959.40

TOTAL \$5786.40

SERVICE

DEPTH OF JOB 5812'

PUMP TRUCK CHARGE \_\_\_\_\_ \$2211.00

EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_

MILEAGE 8.2 mi @ \$7.00 \$574.00

MANIFOLD Head Rental @ \_\_\_\_\_ \$113.00

TOTAL \$2898.00

PLUG & FLOAT EQUIPMENT

1-5/2 Top Rubber Plug \$74.00

1-5/2 Guide Shoe @ \$190.00

1-5/2 Auto-Fill Insert @ \$293.00

1-5/2 Port Collar @ \$1969.00

1-5/2 Basket @ \$186.00

7-5/2 Centralizers @ \$57.00 \$399.00

TOTAL \$3113.00

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

PRINTED NAME MARK KNEELAND