

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20581-00-01
Spot: NWSWSE Sec/Twnshp/Rge: 24-18S-15W
1015 feet from S Section Line, 2399 feet from E Section Line
Lease Name: NORDMAN Well #: 4
County: BARTON Total Vertical Depth: 3548 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	943	0	w/400 sxs cmt
PROD	5.5	3529	0	w/125 sxs cmt <u>115.31</u>

Well Type: EOR UIC Docket No: E17067.1 Date/Time to Plug: 05/19/2009 10:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 275-9231

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 4% gel - 300# hulls.
2 3/8" and 2 7/8" tubing cemented in casing 3059' - will plug through tubing.
Well will take fluid.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2009 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tied to tubing - pumped 75 sxs cement.
Max. P.S.I. 750#. S.I.P. 450#.

Perfs:

Top	Bot	Thru	Comments
3251	3391		

INVOICED
DATE 7-17-09
INV. NO. 2010060031

RECEIVED
JUN 01 2009
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKE #15975.

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

MAY 27 2009

PR


ICER ADDIS
GREAT BEND, KANSAS
CONTR DUKE DRILLING CO.

#4 NORDMAN
CTY BARTON

24-18-15W
NW SW SE

GEOL J. C. MUSGROVE

FIELD ERNA NW



E 1922 KB CM 5/6/71 CARD ISSUED 7/22/71 IP P 115 BOPD N/W
LKC 3391-95
GR 40

API 15-009-20,581

SMP	TOPS	DEPTH	DATUM
ANHY	927	+ 995	
3 ANHY	959	+ 963	
HOW	2852	- 930	
SEV	2906	- 984	
TOP	2925	-1003	
HEEB	3165	-1243	
TOR	3183	-1261	
DDUC	3197	-1275	
BR LM	3237	-1315	
LANS	3246	-1324	
BKC	3470	-1548	
ARB	3508	-1586	
RTD	3534	-1612	
DDTD	3538	-1616	

8 5/8" 943/400sx; 5 1/2" 3529/125sx
DST(1) 3240-60/20-30-20-30, 60' GAS, 30' THIN M W/FEW
GPGTS OIL, BHP 479-436#, FP 17-34#
DST(2) 3294-3423/20-30, 7'M, 18HP 116#, NO FBHP, FP
16-25#
DST(3) 3381-95/30-30-60-30, GTS/23" 1620' CSY OIL
(GR 37.5) BHP 1057-1023#, FP 66-377#
DST(4) 3398-3415/20-30, 10'M, 18HP 42#, NO FBHP, FP
17-17#
DST(5) 3416-30/40", 10'M, 18HP 51#/30"-NO FBHP, FP
17-25#
DST(6) 3514-34/90", 120'HCCM, 180'MO, BHP 893-772#/
30", FP 42-154#
MICT, CO & DD 3538 FU 220' CLEAN OIL, AC 500 SWB 1/2
BOPH, RE-AC 1500 RFC LD SWB 180PH FU 520' OIH, BP 3450
PF 20/3391-95 AC 2000 SWB 36BOPH/3HRS 1500' OB FC 3170
FT OIL N/W(GR 39), POP NO LOG

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS