

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-141-20403-00-00  
Spot: SWNWENW Sec/Twnshp/Rge: 4-9S-15W  
335 feet from N Section Line, 1370 feet from W Section Line  
Lease Name: BEISNER Well #: 1-4  
County: OSBORNE Total Vertical Depth: 3643 feet

Operator License No.: 34225  
Op Name: BUFFALO RESOURCES LLC  
Address: 301 COMMERCE, STE 1380  
FT WORTH, TX 76102

String Size Depth (ft) Pulled (ft) Comment  
SURF 8.625 271

118.40

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/20/2009 12:00 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: STEVE Company: BUFFALO RESOURCES LLC Phone: (620) 786-1878

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 05/20/2009 1:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 1275' w/25 sxs.  
2nd. Plug at 800' w/80 sxs.  
3rd. Plug at 325' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:

INVOICED  
DATE 7-17-09  
INV. NO. 2010060033

RECEIVED  
JUN 01 2009  
KCC WICHITA

Remarks: BASIC CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed CASE MORRIS  
(TECHNICIAN)

PKT