

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-00933-00-00  
Spot: SESESE Sec/Twnshp/Rge: 22-17S-9W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: PRUESS Well #: 1  
County: ELLSWORTH Total Vertical Depth: 3176 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	205		250 SX
PROD	5.5	3166		150 SX <u>103.22</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/19/2009 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/19/2009 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ENCOUNTERED BRIDGE AT APPROX. 800'. BRING IN MUD PUMP AND POWER SWIVEL, DRILLED THRU BRIDGE DOWN TO ANOTHER HARDER STEEL BRIDGE AT APPROX. 1040'. AFTER EFFORT MADE TO DRILL THRU STEEL BRIDGE, DECIDED TO PERFORATE AT 1040', 850', AND 255'. RUN TUBING TO 1040' AND PUMP 35 SX'S CEMENT, LET SET AWHILE AND TAGGED AT 840'. RUN TUBING BACK DOWN TO 820' AND PUMP 35 MORE SACKS CEMENT. PULL TUBING TO 255' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 165 SX'S COMMON CEMENT.

Perfs:

Top	Bot	Thru	Comments
3166	3176	OH	

**INVOICED**  
DATE 7-17-09  
INV. NO. 2010060036

RECEIVED  
JUN 21 2009  
KCC WICHITA

Remarks: USED COMMON CEMENT, COPELAND C-35337. LOG TECH OF KS. TICKET #5737.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

✓sk

PK