

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00934-00-00
Spot: SWSESE Sec/Twnshp/Rge: 22-17S-9W
325 feet from S Section Line, 884 feet from E Section Line
Lease Name: PRUESS Well #: 3
County: ELLSWORTH Total Vertical Depth: 3164 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	205		250 SX
PROD	5.5	3155		150 SX <u>102.83</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/20/2009 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/20/2009 5:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU ON 5-19-2009. ATTEMPT TO RUN BAILER DOWN, HIT OBSTRUCTION AT 1500'-DID RUN ON DOWN TO APPROX. 2000'. RUN NOTCHED TUBING DOWN HOLE CHURNING AND TURNING TO 2015'. ON 5-20-2009, RUN TUBING WITH BIT FROM 2015' TO 2232' THRU SALTY-SANDY-IRON SULFIDE WITH MUD PUMP AND POWER SWIVEL. RAN TUBING DOWN FREELY TO 3100'. PUMPED 50 SX'S COMMON CEMENT. PULL TUBING OUT AND PERFORATE AT 1200', 850', AND 255'. RUN TUBING BACK DOWN TO 1200' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 850' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 255' AND CIRCULATE 60-40 POZ 4% GEL CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. PUMPED 35 SX'S CEMENT ON BACKSIDE OF 5.5" UNTIL PRESSURED UP AND QUIT.

Perfs:

Top	Bot	Thru	Comments
3155	3164	OH	

INVOICED
DATE 7-17-09
INV NO. 2010060036

RECEIVED
JUN 01 2009
KCC WICHITA

Remarks: COPELAND CEMENT #C-35339. LOG TECH OF KANSAS #5739.

Plugged through: TBG

District: 02

Signed _____

Virgil Clothier
(TECHNICIAN)