

15-167-22114-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-167-22,114 ✓

NW SW NW 4 Sec. 13, T 12 S, R 15 W

1650 feet from N/ section line

330 feet from W/ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8572

Lease Name Newman Trust Well # 1

Operator:  
Name & The Reach Group  
Address 3751 E. Douglas  
Wichita, Kansas  
67218

County Russell

Well Total Depth 3163 feet 102.50

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 500'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Reach Drilling License Number 5043

Address same

Company to plug at: Hour: Day: Month: Year: 19

VERBAL PLUGGING ORDERS GIVEN TO Dean Beckner

(company name) Reach Drilling (phone)

were: 1st plug @ 3163' with 20 sacks rat hole 10 sacks

2nd " " 705' " 20 " mouse hole 10 sacks

3rd " " 550' " 40 "

4th " " 250' " 80 "

order 180 sacks 50/50 posmix, 4% gel, 3% CC

Signed (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:45 AM Day: 8 Month: May Year: 1983

ACTUAL PLUGGING REPORT

Remarks: Elevation: 1633', Anhydrite depth: 705'  
did penetrate AR buckle, cemented by Sun cementing

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed David K. Wynn (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION  
INVOICED 5-16-1983  
MAY 16 1983

FORM CP-2/3  
Rev. 9-82

DATE 5-19-83  
INV. NO. 4373-W CONSERVATION DIVISION  
Wichita, Kansas

15-167-22114-00-00

The Reach Group

3751 EAST DOUGLAS • WICHITA, KANSAS 67218 • (316) 683-3626

May 30, 1983

RE: TRG #1 Newman Trust  
NW SW NW  
Sec. 13-T12S-R15W  
Russell Co. Kansas

OPERATOR: THE REACH GROUP  
CONTRACTOR: The Reach Group-Drilling Division  
DRILLING DATES: April 29th, thru May 7th, 1983

Surface pipe set at 500' with 235 sacks of common 3% cc. & 2% Gel


0	663	Sand & Shale
663	705	Shale
705	745	Anhy.
745	1590	Sand & Shale
1590	2460	Shale
2460	3164	Shale & Lime

We certify that the above and foregoing is a true and correct copy of the log on The Reach Group #1 Newman Trust, in Russell Co., Kansas.

THE REACH GROUP-DRILLING DIVISION

Floyd C. Wilson  
President

Subscribed and sworn to before me this 30th day of May, 1983.



*Linda Joyce Overman*  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
7-6-1983  
JUL 08 1983  
CONSERVATION DIVISION  
Wichita, Kansas