

15-167-22975-00-006-25
6 031566

206R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 167-22,975

SE NE NW, SEC. 24, T 12 S, R 15 (W) E

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3293

Lease Name C.J. Steckel Well # 1

Operator: Russell Oil, Inc.

County Russell 98.86

Name & Address P.O. Box 272

Well Total Depth 3042 feet

Russell, Kansas 67665

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Shields Drilling Co., Inc. License Number 5655

Address Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 25 Month: 6 Year: 19 91

Plugging proposal received from Burton Berry

(company name) Shields Drilling Co., Inc. (phone)

were: 8 5/8 set @ 218' w/150 sx. cwc. circ. hole with no less than 36 vis. mud with no loss or gain of fluids. Balance plugs with mud. Order 190 sx. 60/40 poz. 6% gel. 8 5/8 W.P. Allied Cement Company.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:45 P.M. Day: 25 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT Spot plugs with drill pipe with 25 sx. @ 900'.

RECEIVED STATE CORPORATION COMMISSION

8-21-1991 AUG 21 1991

CONSERVATION DIVISION WICHITA, KANSAS

90 sx. @ 660' Halls.

40 sx. @ 218'.

10 sx. @ 40' w/W.P.

circ. 15 sx. in Rathole.

circ. 10 sx. in Mousehole.

Remarks: No Arb. - Elev. 1811 - Anhy. 874-911.

(If additional description is necessary, use BACK of this form.)

I hereby certify that I have observed this plugging.

INVOICED

Signed Carl Goodrow (TECHNICIAN)

DATE SEP 06 1991

INV. NO. 32982