

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-127-20554-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 11-16S-7E
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LEEDS Well #: 1
County: MORRIS Total Vertical Depth: 1769 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	184		120 SX
PROD	4.5	1653		150 SX

57.49

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2009 1:00 PM
Plug Co. License No.: 5010 Plug Co. Name: KNIGHTON OIL COMPANY, INC.
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL CO. Phone: (785) 623-4081

Proposed Plugging Method: SET CIBP ABOVE TOP PERFS AND CAP WITH SX CEMENT. PERFORATE CASING AT 250' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2009 4:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

SET CIBP AT 1370' AND CAPPED WITH 2 SX CEMENT. PERFORATED CASING AT 250'. PUMPED 100 SX CEMENT TO CIRCULATE TO SURFACE. (CASING WAS MIT'D PRIOR TO PERFORATING CASING).

Perfs:

Top	Bot	Thru	Comments
1414	1420		

INVOICED

DATE 7-20-09

INV. NO. 2010060039

RECEIVED

JUN 01 2009

KCC WICHITA

Remarks: CONSOLIDATED TICKET #20927 TOTAL = 100 SX 60/40 POZ 4% GEL.

Plugged through: CSG

District: 02

Signed Greg Eves
(TECHNICIAN)