

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24974-00-00
Spot: NESESW Sec/Twnshp/Rge: 1-20S-13W
950 feet from S Section Line, 2500 feet from W Section Line
Lease Name: ROGERS Well #: 1-1
County: BARTON Total Vertical Depth: 3535 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3265		
SURF	8.625	673	0	400 SX CMT.
T1	2.375	3251		125 SX CMT.
PROD	5.5	3534	2610	w/125 sxs cmt

114.89

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/14/2009 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Company ordered all cement plug.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/14/2009 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off bottom and dumped 5 sxs cement on top.
Cut casing at 2610' - pulled to 1813' - pumped 125 sxs cement with 300# hulls.
Pulled 700' - pumped 50 sxs cement with 100# hulls.
Pulled to 250' - pumped 100 sxs cement with 100# hulls - cement circulated to surface.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3453	3458		
3447	3451		
3437	3440		
3269	3276		
3255	3259		
3229	3236		
3220	3224		

INVOICED
DATE 7-20-09
INV. NO. 2010060041
RECEIVED
JUN 01 2009
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #35336.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

MAY 27 2009

PR

MURFIN DRILLING CO
WICHITA KS 67202

WILDCAT

1-20S-13W
950' FSL & 2500' FWL, SEC

#1-1 ROGERS

site: 3/4 S & 1-3/4 E OF GREATBEND KS
cont: MURFIN DRILLING #8
cust: PATRICK J. DEENIHAN
fr date 08/15/2006
spc date 08/18/2006
orig comp 08/27/2006
dy: BARTON
field: WC (SUNNY VALLEY SCHOOL DISC)
API 15-009-24974
card issued 01/08/2007
last revised 01/08/2007

ELV: 1841 KB, 1836 GL
tops.....depth/datum
PBD.....3491 -1650
RTD.....3535 -1694
NO TOPS RPTD

IP status:
OIL, LKC, ARB, INTV NA, 10/25/2006
CSG: 8-5/8" 673 / 400 SX (ALT 1), 5-1/2" 3534 / 125 SX
NO CORES
DSTS TAKEN - DETAILS NA
TRGT ZN: LKC, ARB (OIL/GAS), PTD 3500 (ARB), MICT -
CO, PB 3491, PF (ARB) INTV NA, SWB DWN, GSO, PF (LKC)
INTV NA, AC'D, SWB LD, GSO, POP, OIL WELL
(POTENTIAL NOT RPTD), 10/25/2006 - TIGHT HOLE - NO
OTHER INFO AVAILABLE - TEMP COMP 1/8/2007

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS